PROJECT NO.	SHEET NO.	TOTAL NO.
10CR.10131.38, ETC	17	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	SOIL CEMENT BASE (FULL DEPTH RECLAMATION) SY	PORTLAND CEMENT FOR SOIL CEMENT BASE TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	4" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	INTERMEDIATE COURSE, I19.0C TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE) TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREAT-MENT, SINGLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREAT-MENT GAL	2'-6" CURB & GUTTER LF	4" CONC SIDE-WALK SY	CONC CURB RAMPS EA	6" DRIVE WAYS SY	RETROFIT EXISTING CURB RAMPS EA	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOXES EA	TEMP SILT FENCE LF	WATTLE LF
10CR.10131.38	Cabarrus	1	NC 3	FROM SR 1691 (LOOP RD) TO SR 1008 (US 29 A) MILEPOST 10.12 TO 10.98	1,2	4	NO	NO	0.86	56						28,900								2,616				154	350			60	35	20		14	3	1		
10CR.10131.39	Cabarrus	2	US 29	NC 73 TO SR 1414 (ROCK HILL CH RD) EXCLUDE SUPERSTREET PROJECT MILEPOST 5.43 TO 8.32	3,4,5,6	4	NO	NO	2.89	28'-100'						120,680								12,106				714	1,000								10	10	1,500	
10CR.20131.119	Cabarrus	3	SR 1394 (POPLAR TENT RD)	FROM PAVEMENT JOINT E OF SR 1448 (COX MILL RD) TO PAVEMENT JOINT @ 1-85 PROJECT MILEPOST 6.46 TO 6.90	12	2	NO	NO	0.44	23	50				0.88				110					607				36	200										50	100
10CR.20131.119	Cabarrus	4	SR 1394 (POPLAR TENT RD)	FROM PAVT JT E OF CARO INTER. SCH. TO PAVT JT W OF SR 1448 (COX MILL RD) MILEPOST 7.21 TO 7.37	12	2	NO	NO	0.16	23	20				0.32				110					201				12	50										50	50
10CR.20131.119	Cabarrus	5	SR 1394 (POPLAR TENT ROAD)	FROM 100 FEET WEST OF SR 1449 (HARRIS ROAD) TO PAVEMENT JOINT @ CAROLINA INTER. SCH. MILEPOST 7.59 TO 8.23	12,20	2	NO	NO	0.64	23	88				0.83			1,067	110					1,429	200			97	240								5	5	200	200
TOTAL FOR PROJ NO. 10CR.20131.119									1.24		158				2.03			1,067	330					2,237	200			145	490								5	5	300	350
10CR.20131.120	Cabarrus	6	SR 2710 (WALKER RD)	FROM NC 73 TO NC 49 MILEPOST 0.00 TO 1.44	7	2	NO	NO	1.44	20	200				2.88				110			1,626	400					124	500										200	200
10CR.20131.121	Cabarrus	7	SR 1157 (WILSHIRE DR)	FROM SR 1335 (OLD CHARLOTTE RD) TO US 601 MILEPOST 1.82 TO 2.74	13,14	2	NO	NO	0.92	20'-36'	100			46	1.40	10,200	2,000			316		2,023						137	300								2	6	100	240
10CR.20131.122	Cabarrus	8	SR 2408 (GOLD HILL RD)	FROM NC 73 TO SR 2411 (IRISH POTATO RD) MILEPOST 0.00 TO 2.99	7,9	2	NO	NO	2.99	24'-80'	598				5.98			560	350			4,240	300					274	1,000										200	560
10CR.20131.123	Cabarrus	9	SR 1153 (ZION CH RD EAST)	FROM US 601 TO SR 1155 (ZION CH RD) MILEPOST 0.00 TO 1.58	7,8	2	NO	NO	1.58	20'-42'	200				3.16	500		500	500			2,387	300					163	350						60		1	8	200	480
10CR.20131.124	Cabarrus	10	SR 1002 (CABARRUS AVE)	FROM US 601 US 29 MILEPOST 9.30 TO 9.52	1,18	2	NO	NO	0.22	60'-72'						8,800								849				50	350								1	1		
10CR.20131.118	Cabarrus	11	SR 2433 (PHANIELS CH RD)	FROM SR 2429 (RIMER RD) TO ROWAN COUNTY LINE MILEPOST 0.00 TO 1.08	15	2	NO	NO	1.08	20'																880	100	65												
10CR.20131.125	Cabarrus	12	SR 2604 (DUTCH RD)	FROM PAVEMENT JOINT 1700 FEET NORTH OF NC 73 TO SR 2444 (CRUSE RD)	16	2	NO	NO	3	20'-23'		38,720	1,200						110							2,400	100	167		35,200	12,320									
10CR.20131.126	Cabarrus	13	SR 1127 (SAM BLACK RD)	FROM NC 24/27 TO SR 1132 (FLOWES STORE RD) MILEPOST 0.00 TO 2.69	7,11	2	NO	NO	2.69	21'-96'	275				5.38	500						6,562	150					404												
10CR.20131.127	Cabarrus	14	SR 2402 (SAPP RD)	FROM ROWAN COUNTY LINE TO SR 2400 (IRISH POTATO RD) MILEPOST 0.00 TO 1.73	17	2	NO	NO	1.73	21'-22'																1,506	200	113												
10CR.20131.117	Cabarrus	15	SR 1441 (GOODMAN RD)	FROM PAVEMENT ON SR 1441 (GOODMAN RD) TO END OF PAVEMENT INCLUDING Y LINE MILEPOST 0.09 TO 1.30	19	2	NO	NO	1.21	24'	800				2.42						3,238			2,334				293												
10CR.20131.128	Cabarrus	16	SR 2350 (MILLEN DR)	SR 1139 (ROCKY RIVER RD) TO END OF PAVEMENT MILEPOST 0.00 TO 0.58	10	2	NO	NO	0.58	30'								4,920				1,005						60	250								1	1		
10CR.20131.129	Cabarrus	17	SR 2353 (MYERS LN)	FROM SR 2350 (MILLEN DR) TO END OF PAVEMENT MILEPOST 0.14 TO 0.40	11	2	NO	NO	0.26	22'						3,400						334						20	150								1	1		
GRAND TOTAL									**22.69**		**2,331**	**38,720**	**1,200**	**46**	**23.25**	**172,980**	**2,000**	**7,047**	**1,400**	**316**	**3,238**	**18,177**	**1,150**	**20,142**	**200**	**4,786**	**400**	**2,883**	**4,740**	**35,200**	**12,320**	**60**	**35**	**20**	**60**	**14**	**24**	**33**	**2,500**	**1,830**