PROJECT NO.	SHEET NO.	TOTAL NO.
10CR.10131.38, ETC	18	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000 WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	445700000 TEMPORARY TRAFFIC CONTROL LS	451000 LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	8" X 90 M YELLOW THERMO LF	46970000 8" X 120 M WHITE THERMO LF	47000000 12" X 90 M YELLOW THERMO LF	47100000 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO LT STR RT ARROW 90 M EA	4770000000-E YELLOW COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II (4") LF	WHITE COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE II (4") LF	4810000000-E 4" WHITE PAINT LF	4" YELLOW PAINT LF	4835000 24" WHITE PAINT LF	48500000 4" LINE REMOVAL LF	4900000000-N CRYSTAL & RED MARKERS EA	YELLOW & YELLOW MARKERS EA
10CR.10131.38	Cabarrus	1	NC 3	FROM SR 1691 (LOOP RD) TO SR 1008 (US 29 A) MILEPOST 10.12 TO 10.98	1,2	4	0.86	56'	86		30			4,500	7,960			650	400	175			30	12	12					4,541	7,960			150	120
10CR.10131.39	Cabarrus	2	US 29	NC 73 TO SR 1414 (ROCK HILL CH RD) EXCLUDE SUPERSTREET PROJECT MILEPOST 5.43 TO 8.32	3,4,5,6	4	2.89	28'-100'	286		50	32,000	32,000	14,500		1,100				1,015	4		52	40	7	23				15,259	16,000	1,015		1,400	
10CR.20131.119	Cabarrus	3	SR 1394 (POPLAR TENT RD)	FROM PAVEMENT JOINT E OF SR 1448 (COX MILL RD) ON SR 1394 (POPLAR TENT RD) TO PAVEMENT JOINT @ 1-85 PROJECT MILEPOST 6.46 TO 6.90	12	2	0.44	23'	86			4,660			4,660																				
10CR.20131.119	Cabarrus	4	SR 1394 (POPLAR TENT RD)	FROM PAVT JT E OF CARO INTER. SCH. SR 1394 (POPLAR TENTRD) TO PAVT JT W OF SR 1448 (COX MILL RD) ON SR 1394 (POPLAR TENT RD) MILEPOST 7.21 TO 7.37	12	2	0.16	23'	54			1,654			1,654					50		6														
10CR.20131.119	Cabarrus	5	SR 1394 (POPLAR TENT ROAD)	FROM 100 FEET WEST OF SR 1449 (HARRIS ROAD) TO PAVEMENT JOINT @ CAROLINA INTER. SCH. ON SR 1394 (POPLAR TENT RD) MILEPOST 7.59 TO 8.23	12,20	2	0.64	23'-46'	86			5,700		1,600	9,600	150	200			260		6	14	3	2	5										
TOTAL FOR PROJ NO. 10CR.20131.119							1.24		226			12,014		1,600	15,914	150	200			310		12	14	3	2	5									
10CR.20131.120	Cabarrus	6	SR 2710 (WALKER RD)	FROM NC 73 TO NC 49 MILEPOST 0.00 TO 1.44	7	2	1.44	20'	118																											
10CR.20131.121	Cabarrus	7	SR 1157 (WILSHIRE DR)	FROM SR 1335 (OLD CHARLOTTE RD) TO US 601 MILEPOST 1.82 TO 2.74	13,14	2	0.92	20'-36'	102	*	20	7,700		300	9,600		150			50			5		2			700	350	500	9,600	50	1,050		
10CR.20131.122	Cabarrus	8	SR 2408 (GOLD HILL RD)	FROM NC 73 TO SR 2411 (IRISH POTATO RD) MILEPOST 0.00 TO 2.99	7,9	2	2.99	24'-80'	222		10	32,172		320	19,734					35			2			2									
10CR.20131.123	Cabarrus	9	SR 1153 (ZION CH RD EAST)	FROM US 601 TO SR 1155 (ZION CH RD) MILEPOST 0.00 TO 1.58	7,8	2	1.58	20'-42'	204		15	17,001		730	20,061		330						10			2									
10CR.20131.124	Cabarrus	10	SR 1002 (CABARRUS	FROM US 601 US 29 MILEPOST 9.30 TO 9.52	1,18	2	0.22	60'-72'	118		20			1,050	1,800					200	4		12	6	1	3	1			1,800	1,050	200			
10CR.20131.118	Cabarrus	11	SR 2433 (PHANIELS CH RD)	FROM SR 2429 (RIMER RD) TO ROWAN COUNTY LINE MILEPOST 0.00 TO 1.08	15	2	1.08	20'	86																											
10CR.20131.125	Cabarrus	12	SR 2604 (DUTCH RD)	FROM PAVEMENT JOINT 1700 FEET NORTH OF NC 73 TO SR 2444 (CRUSE RD)	16	2	3	20'-23'	182																											
10CR.20131.126	Cabarrus	13	SR 1127 (SAM BLACK RD)	FROM NC 24/27 TO SR 1132 (FLOWES STORE RD) MILEPOST 0.00 TO 2.69	7,11	2	2.69	21'-96'	182																											
10CR.20131.127	Cabarrus	14	SR 2402 (SAPP RD)	FROM ROWAN COUNTY LINE TO SR 2400 (IRISH POTATO RD) MILEPOST 0.00 TO 1.73	17	2	1.73	21'-22'	134																											
10CR.20131.117	Cabarrus	15	SR 1441 (GOODMAN RD)	FROM PAVEMENT ON ON SR 1441 (GOODMAN RD) TO END OF PAVEMENT INCLUDING Y LINE MILEPOST 0.09 TO 1.30	19	2	1.21	24'	118																											
10CR.20131.128	Cabarrus	16	SR 2350 (MILLEN DR)	SR 1139 (ROCKY RIVER RD) TO END OF PAVEMENT MILEPOST 0.00 TO 0.58	10	2	0.58	30'	54																											
10CR.20131.129	Cabarrus	17	SR 2353 (MYERS LN)	FROM SR 2350 (MILLEN DR) TO END OF PAVEMENT MILEPOST 0.14 TO 0.40	11	2	0.26	22'	54																											
GRAND TOTAL							**22.69**		**2,172**	**1**	**145**	**100,887**	**32,000**	**23,000**	**75,069**	**1,250**	**680**	**650**	**400**	**1,785**	**8**	**12**	**125**	**61**	**24**	**35**	**1**	**700**	**350**	**22,100**	**34,610**	**1,265**	**1,050**	**1,550**	**120**
												132,887		**98,069**		**1,930**					**20**		**246**					**1,050**		**56,710**				**1,670**