Undivided coastal plain soils were encountered beneath the alluvial soils. They are comprised of 20 or more feet of loose to very dense sand (A-2-4, A-3), 1± foot of loose sand with trace to little organic material (A-2-5), and 5± feet of soft to medium stiff clay (A-6).

Laboratory analysis of these soils show organic percentages ranging from 2% to 3% and moisture contents ranging from 23% to 52%.

Undisturbed Samples

Undisturbed thin wall Shelby tube samples were collected at the following locations and submitted for testing.

Sample No.	Station	Depth	Test
ST-1	-L- 56+00 25' RT	19.7-21.7	Consolidation/ Triaxial
ST-2	-L- 56+00 25' RT	24.7-26.7	Consolidation/ Triaxial
ST-3	-L- 36+00 24' RT	17.0-18.7	Consolidation/ Triaxial
ST-4	-L- 36+00 24' RT	19.0-20.7	Consolidation/ Triaxial
ST-5	-L- 56+50 25' LT	6.1-8.1	Consolidation/ Triaxial
ST-6	-L- 56+50 25' LT	8.1-10.1	Consolidation/ Triaxial
ST-7	-L- 58+53 27' LT	6.5-8.5	Consolidation/ Triaxial
ST-8	-L- 58+53 27' LT	8.5-10.5	Consolidation/ Triaxial
ST-9	-L- 60+49 36' LT	7.5-9.5	Consolidation/ Triaxial
ST-10	-L- 60+49 36' LT	9.5-11.5	Consolidation/ Triaxial
ST-11	-L- 62+50 45' LT	9.0-11.0	Consolidation/ Triaxial
ST-12	-L- 62+50 45' LT	11.0-13.0	Consolidation/ Triaxial
ST-13	-L- 35+08 41' LT	6.5-8.5	Consolidation/ Triaxial
ST-14	-L- 35+08 41' LT	8.5-10.5	Consolidation/ Triaxial
ST-15	-L- 37+00 25' LT	6.5-8.5	Consolidation/ Triaxial
ST-16	-L- 37+00 25' LT	8.5-10.5	Consolidation/ Triaxial
ST-17	-L- 39+00 25' LT	4.0-6.0	Consolidation/ Triaxial
ST-18	-L- 39+00 25' LT	6.0-8.0	Consolidation/ Triaxial
ST-19	-L- 41+00 18' LT	6.5-8.5	Consolidation/ Triaxial
ST-20	-L- 41+00 18' LT	8.5-10.5	Consolidation/ Triaxial
ST-21	-L- 54+49 4' RT	14.0-15.0	Consolidation/ Triaxial
ST-22	-L- 54+49 4' RT	18.0-20.0	Consolidation/ Triaxial
ST-23	-L- 54+49 4' RT	20.0-22.0	Consolidation/ Triaxial

Respectfully Submitted,

Tyler C. Bottoms, L.G.
Project Engineering Geologist