PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10361.19, 12CR.20361.27	18	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	3" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	LEVELING COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	RETROFIT EXISTING CURB RAMP EA	CONCRETE CURB RAMP EA	ADJ. OF CATCH BASINS EA	ADJ. OF DROP INLETS EA	ADJ. OF MAN-HOLES EA	ADJ. OF METER OR VALVE BOXES EA	CONVERT EXISTING DROP INLET TO CATCH BASIN EA	FRAME WITH GRATE & HOOD, TYPE 'E' EA	PORTABLE LIGHTING LS
12CR.10361.19	Gaston	1	NC-279 (LOWER DALLAS HWY)	NC-275 TO BEGIN GORE MULTI-LANE	1 2	2 2	NO	NO	1.15 0.23	VAR. 25-36 VAR. 24-42	445	10	2.53	4,300		350		2,342	118			148	351					3	4			*
TOTAL FOR MAP NO. 1									1.38																							
12CR.10361.19	Gaston	2	NC-275 (DALLAS-BESSEMER CITY HWY)	BRIDGE TO 793' S of NC-279	1	2	NO	NO	1.38	VAR. 24-37	485	30	2.76			420		2,007	139			129	301									
12CR.10361.19	Gaston	3	NC-273 (N MAIN ST.)	NIMS AVE. TO LANIER ST.	3 4 5	2 2 2	NO	NO	0.21 0.18 0.43	VAR. 23-24 VAR. 24-36 26				14,788				1,250	115			82	345			4		27	14	3	3	*
TOTAL FOR MAP NO. 3									0.82																							
12CR.10361.19	Gaston	4	US-321 (YORK RD)	SR-1157 TO SR-1255 (HUDSON BLVD)	6 7	4 4	NO	NO	0.46 0.08	VAR. 41-44 VAR. 44-75				16,184						1,368	123	89	230	4				12	5	3	3	*
TOTAL FOR MAP NO. 4									0.54																							
12CR.10361.19	Gaston	5	NC-7 (LONG AVENUE)	US-321 TO I-85 BRIDGE	4 8 9	5 4 4	NO	NO	1.67 0.05 0.05	VAR. 61-62 VAR. 60-74 VAR. 60-74				69,953				5,913	295			374	595	24	2	1	2	20	3			*
TOTAL FOR MAP NO. 5									1.77																							
TOTAL FOR PROJ NO. 12CR.10361.19									**5.89**		**930**	**40**	**5.29**	**105,225**		**770**		**11,512**	**667**	**1,368**	**123**	**822**	**1,822**	**28**	**2**	**5**	**2**	**62**	**26**	**6**	**6**	
12CR.20361.27	Gaston	6	SR-1622 (HEPHZIBAH CH RD)	SR-1438 TO SR-1625	1	2	NO	NO	0.64	VAR. 20-21	224	20	1.28			140		709	92			48	156									
12CR.20361.27	Gaston	7	SR-1625 (WILL KISER RD)	SR-1622 TO SR-1617	1	2	NO	NO	0.76	VAR. 19-20	266	22	1.52			70		829	95			56	191									
12CR.20361.27	Gaston	8	SR-1616 (GASTON WEBBS CHAPEL RD)	SR-1609 TO LINCOLN CO LINE	1	2	NO	NO	0.24	19	84	15	0.48			140		249	38			17	130									
12CR.20361.27	Gaston	9	SR-1453 (JOE CLONIGER RD)	SR-1452 TO SR-1452	12	2	NO	NO	1.61	VAR. 20-22	565	90	3.22			140	728	1,844	334			164	480									
12CR.20361.27	Gaston	10	SR-1452 (COSTNER SCHOOL RD)	270 FT N OF NC-274 TO 200 FT N OF BRIDGE	12	2	NO	NO	2.14	20	749	60	4.28			470	968	2,335	352			206	654									
12CR.20361.27	Gaston	11	SR-1106 (FREEDOM MILL RD)	SR-1103 TO SR-1126	1	2	NO	NO	1.26	VAR. 20-21	266	50	1.52			280		1,443	145			96	418									
12CR.20361.27	Gaston	12	SR-1109 (FERGUSON RIDGE RD)	SR-1108 TO SC STATE LINE	1	2	NO	NO	1.35	VAR. 21-22	473	50	2.70			620		1,619	114			105	502									
12CR.20361.27	Gaston	13	SR-1103 (CROWDERS CREEK RD)	SR-1130 TO US-321 (SKIP NEW BRIDGE PVMT SECTION)	1	2	NO	NO	1.88	22	658	70	3.76			100		2,255	135			144	677									
12CR.20361.27	Gaston	14	SR-2490 (CRAMER MTN RD)	NC-279 TO SR-2014	4 1 2 10 5	4 2 2 2 2	NO	NO	0.19 0.60 0.48 0.14 0.14	VAR. 37-46 VAR. 22-25 VAR. 22-23 VAR. 23-27 VAR. 27-29	294		1.68	15,037	2,440	570		2,245	225			149	427					3				
TOTAL FOR MAP NO. 14									1.55																							
12CR.20361.27	Gaston	15	SR-2084 (KEE RD)	US-29/74 TO NC-7	1	2	NO	NO	0.47	19	165	10	0.94			210		487	39			32	300						1			
12CR.20361.27	Gaston	16	SR-1935 (WILLOWSIDE)	SR-1918 TO SR-1923	1	2	NO	NO	1.46	21	511	20	2.92			590		1,672	215			114	452									
12CR.20361.27	Gaston	17	SR-1922 (W DALLAS RD)	NC-27 TO NC-275	1 11	2	NO	NO	0.30 0.03	VAR. 23-40 VAR. 24-42	105	40	0.60			650		451	50			30	100					3				
TOTAL FOR MAP NO. 17									0.33																							
12CR.20361.27	Gaston	18	SR-2085 (LANE RD)	SR-2000 TO SR-1924	4 1	3 2	NO	NO	0.03 1.72	35 VAR. 24-25	602	15	3.44	615		140		2,355	118			149	590									
TOTAL FOR MAP NO. 18									1.75																							
TOTAL FOR PROJ NO. 12CR.20361.27									**15.44**		**4,962**	**462**	**28.34**	**15,652**	**2,440**	**4,120**	**1,696**	**18,493**	**1,952**			**1,310**	**5,077**					**6**	**1**			
GRAND TOTAL									**21.33**		**5,892**	**502**	**33.63**	**120,877**	**2,440**	**4,890**	**1,696**	**30,005**	**2,619**	**1,368**	**123**	**2,132**	**6,899**	**28**	**2**	**5**	**2**	**68**	**27**	**6**	**6**	**1**