STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

McDOWELL COUNTY
B–3673

CROSS SECTION SUMMARY

QUANTITIES ARE APPROXIMATE ONLY. THE RESIDENT ENGINEER WILL RE-CROSS-SECTION THE WORK ACCURATELY WHEN THE PROJECT IS STAKED OUT. THESE CROSS-SECTION NOTES WILL BE USED IN COMPUTING THE FINAL QUANTITIES FOR WHICH THE CONTRACTOR WILL BE PAID.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+15.00	0	0	25+00.00	2841	116
12+50.00	59	241	25+50.00	6752	97
13+00.00	132	806	26+00.00	9098	67
13+50.00	103	964	26+50.00	9592	65
14+00.00	82	1048	27+00.00	10934	83
14+50.00	78	1048	27+50.00	11301	121
15+00.00	73	935	27+78.00	5383	106
15+50.00	70	763	30+98.00	0	0
16+00.00	78	581	31+00.00	9	59
16+50.00	76	457	31+50.00	245	1466
17+00.00	175	400	32+00.00	276	1454
17+50.00	1909	274	32+50.00	206	1453
18+00.00	5770	138	33+00.00	71	1399
18+50.00	8114	53	33+50.00	33	1189
19+00.00	6483	12	34+00.00	58	925
19+50.00	4116	21	34+50.00	60	685
20+00.00	5428	25	35+00.00	64	472
20+50.00	8118	16	35+50.00	45	319
21+00.00	7155	13	36+00.00	19	266
21+50.00	3141	13	36+50.00	16	290
22+00.00	619	144	37+00.00	15	267
22+50.00	1341	168	37+50.00	17	127
23+00.00	2648	69	38+00.00	16	32
23+50.00	2907	100	38+50.00	14	33
24+00.00	2290	121	39+00.00	18	16
24+50.00	1397	115	39+15.00	5	2

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

8/17/99
REVISIONS
1/22/2015 1:50:10 PM
R:\Roadway\Proj\B-3673_Rdy_INDEX_xpl.dgn
USER: toddbuckner