| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| B-5124 | SIGN-1 |

APPROVED: DocuSigned by: Ayman Alqudwah F32AC5CAF965472...

DATE: 1/5/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 028387 ENGINEER AYMAN I. ALQUDWAH

# STATE OF NORTH CAROLINA
# DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN
# NASH COUNTY

### LOCATION: BRIDGES 141, 151, AND 85 OVER SWIFT CREEK ON US 301

T.I.P.: B-5124

CONTRACT: C203564

## SUMMARY OF QUANTITIES

| ITEM NO. DESC. NO. | ITEM NO. SECT. NO. | ITEM DESCRIPTION | QUANTITY | UNIT |
|---|---|---|---|---|
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 55 | LF. |
| 4096000000 | 904 | SIGN ERECTION, TYPE D | 2 | EA. |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 4 | EA. |
| 4155000000 | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 10 | EA. |

## GENERAL NOTES

. SIGNS FURNISHED BY STATE
. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 903.10 | GROUND MOUNTED SIGN SUPPORTS |
| 904.30 | SUPPLEMENTAL SIGN MOUNTING |
| 904.50 | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |

## PROJECT NOTES

| | |
|---|---|
| 1 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL |

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

AYMAN ALQUDWAH, P.E. — SIGNING & DELINEATION REGIONAL ENGINEER

ERIC E WARD — SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

## INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| SIGN - 1 | TITLE SHEET |
| SIGN - 2 | TYPE D & E SIGNS SHEET |
| SIGN - 3-5 | SIGN DETAIL SHEETS |


1/5/2015
P:\TIPProjects-B\B5124\Traffic\Signing\CADD\Signing Layout Plans\b5124_sgn_psh_s01.dgn
User:ericward