PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10931.15, 5CR.20931.15	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC
5CR.10931.15	Warren	1	NC 58	FRANKLIN CO LINE TO NC 43	1,3	2	2WU	NO	NO	11.3	18-24	2,260	565	22.60	1,000	317	11,214		687	75	1	1,595	3,990	16.39
5CR.10931.15	Warren	2	NC 43	HALIFAX CO LINE TO NC 58	3	2	2WU	NO	YES	10.1	20-21	2,020	505	20.20	1,000		10,606		636	75		1,450	3,630	14.65
TOTAL FOR PROJ NO. 5CR.10931.15										**21.4**		**4,280**	**1,070**	**42.80**	**2,000**	**317**	**21,820**		**1,323**	**150**	**1**	**3,045**	**7,620**	**31.04**
5CR.20931.15	Warren	3	SR 1325 - AIRPORT RD	US 158 BUS TO SR 1305 - WARREN PLAINS RD	2	2	2WU	NO	NO	2.5	20	500	125	5.00	1,800			2,129	143	40		363	910	3.63
5CR.20931.15	Warren	4	SR 1318 - OLD MACON HWY	SR 1500 - MACON-EMBRO RD TO END OF MAINT., EXCLUDING NONPAVED SECTION FROM SR 1335 TO SR 1325	2	2	2WU	NO	NO	4.4	20	880	220	8.80	775			3,746	251	25		522	1,310	6.38
5CR.20931.15	Warren	5	SR 1431 - MILL CREEK DR	NC 903 - EBONY RD TO END OF MAINT.	2	2	2WU	NO	NO	1.18	18	236	59	2.36	325			905	61	30		171	430	1.71
5CR.20931.15	Warren	6	SR 1118 - NO BOTTOM RD	SR 1112 - AXTELL RIDGEWAY RD TO SR 1107 - RIDGEWAY WARRENTON RD	2	2	2WU	NO	NO	4.23	20	846	212	8.46	870			3,601	241	50		613	1,540	6.13
5CR.20931.15	Warren	7	SR 1100 - MANSON-AXTELL RD	SR 1001 - MARTIN LUTHER KING BLVD TO SR 1102 - COLLINS RD	2	2	2WU	NO	YES	4.5	20	900	225	9.00	720			3,812	255	70		652	1,630	6.53
TOTAL FOR PROJ NO. 5CR.20931.15										**16.81**		**3,362**	**841**	**33.62**	**4,490**			**14,193**	**951**	**215**		**2,321**	**5,820**	**24.38**
GRAND TOTAL										**38.21**		**7,642**	**1,911**	**76.42**	**6,490**	**317**	**21,820**	**14,193**	**2,274**	**365**	**1**	**5,366**	**13,440**	**55.42**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4685000000-E 4" X 90 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4770000000-E 4" WHITE COLD APPLIED PLASTIC, TYPE III LF	4770000000-E 4" YELLOW COLD APPLIED PLASTIC, TYPE III LF	4850000000-E 4" LINE REMOVAL LF	4900000000-N YELLOW & YELLOW MARKERS EA
5CR.10931.15	Warren	1	NC 58	FRANKLIN CO LINE TO NC 43	1,3	2	2WU	11.3	18-24	1,232	0.30	121,588	74,580	75	270	270	540	746
5CR.10931.15	Warren	2	NC 43	HALIFAX CO LINE TO NC 58	3	2	2WU	10.1	20-21	1,120	0.27	108,676	66,660	75				667
TOTAL FOR PROJ NO. 5CR.10931.15								**21.4**		**2,352**	**0.57**	**230,264**	**141,240**	**150**	**270**	**270**	**540**	**1,413**
													141,390		**540**			
5CR.20931.15	Warren	3	SR 1325 - AIRPORT RD	US 158 BUS TO SR 1305 - WARREN PLAINS RD	2	2	2WU	2.5	20	280	0.07	26,900	16,500	15				
5CR.20931.15	Warren	4	SR 1318 - OLD MACON HWY	SR 1500 - MACON-EMBRO RD TO END OF MAINT., EXCLUDING NONPAVED SECTION FROM SR 1335 TO SR 1325	2	2	2WU	4.4	20	403	0.10	47,344	29,040	30				
5CR.20931.15	Warren	5	SR 1431 - MILL CREEK DR	NC 903 - EBONY RD TO END OF MAINT.	2	2	2WU	1.18	18	133	0.03	12,697	7,788	23				
5CR.20931.15	Warren	6	SR 1118 - NO BOTTOM RD	SR 1112 - AXTELL RIDGEWAY RD TO SR 1107 - RIDGEWAY WARRENTON RD	2	2	2WU	4.23	20	474	0.11	45,515	27,918	30				
5CR.20931.15	Warren	7	SR 1100 - MANSON-AXTELL RD	SR 1001 - MARTIN LUTHER KING BLVD TO SR 1102 - COLLINS RD	2	2	2WU	4.5	20	504	0.12	48,420	29,700	53	300	300	600	
TOTAL FOR PROJ NO. 5CR.20931.15								**16.81**		**1,794**	**0.43**	**180,876**	**110,946**	**151**	**300**	**300**	**600**	
													111,097		**600**			
GRAND TOTAL								**38.21**		**4,146**	**1.00**	**411,140**	**252,186**	**301**	**570**	**570**	**1,140**	**1,413**
													252,487		**1,140**			