CONTACT INFORMATION FOR UTILITIES

POWER: DUKE POWER- JB JONES, 910-206-1966, JB.JONES@DUKE-ENERGY.COM
6" WATER & SEWER: CAMPBELL UNIVERSITY- SCOT PHILLIPS, 910-893-1610, PHILLIPSS@CAMPBELL.EDU
12" & 20" WATER: HARNETT COUNTY- SHANE CUMMINGS, 910-893-7575X3275, SCUMMINGS@HARNETT.ORG
COMMUNICATIONS: CAMPBELL UNIVERSITY- EARL SAVAGE, 910-893-1610, SAVAGE@CAMPBELL.EDU
CABLE: TIME WARNER CABLE (TWC)- JACK CRABB, 910-401-5034, JACK.CRABB@TWCABLE.COM
CABLE: CHARTER- DARREN MCCLUNG, 910-813-1618, DARREN.MCCLUNG@CHARTER.COM
TELEPHONE: CENTURYLINK- KEVIN GODWIN, 910-336-2142, KEVIN.GODWIN@CENTURYLINK.COM
GAS: PIEDMONT NG, JIMMIE WOOD, 919-705-5054, JIMMIE.WOOD@PIEDMONTNG.COM

CH ENGINEERING
3220 GLEN ROYAL RD. RALEIGH, NC 27617
TELE 919.788.0224 FAX 919.788.0232
NC LICENSE #P-0189

PROJECT REFERENCE NO.	SHEET NO.
W5206AG	UO-3

UTILITIES BY OTHERS

NOTE:
ALL PROPOSED UTILITY WORK SHOWN ON THIS SHEET WILL BE DONE BY OTHERS

NC GRID
NAD 83/2001

40 0 20 40 80

12" TC SEWER & 6" PVC WATER TO BE ABANDONED

CAMPBELL INSTALLED 6" DIP WATER

CAMPBELL INSTALLED NEW 12" DIP SEWER

NEW GAS BY PIEDMONT NG AT 5' OFFSET FROM 6" WL AND 15" RCP DRAINAGE

CAMPBELL DEEP-BORED CONDUIT FOR COMMUNICATIONS SHARED WITH CHARTER

TIME WARNER TO RELOCATE FOC

CAMPBELL PROVIDED UTILITY VAULT FOR COMMUNICATIONS SHARED WITH CHARTER CABLE.

TWC TO RELOCATE FOC PRIOR TO CONSTRUCTION BY BORING AT A DEPTH OF 20'+ TO GET BENEATH PROPOSED CULVERT.

PIEDMONT NG TO RECONNECT NEW GAS LINES TO EXISTING GAS LINES

CENTURYLINK TO ABANDON EXISTING CABLES

CENTURYLINK TO INSTALL NEW Cu AND FOC CABLES

DUKE TO BURY NEW POWER TO EX. STREET LIGHTS.

CENTURYLINK TO INSTALL NEW Cu AND FOC CABLES APPROX. 2' INSIDE PUE

PIEDMONT NG TO ABANDON THE EXISTING GAS LINES

CENTURYLINK TO ABANDON EXISTING CABLES

PIEDMONT NG TO INSTALL (2) NEW STEEL GAS LINES INSIDE PUE. APPROX. 4-6' OUTSIDE ROW

DUKE ENERGY TO PROVIDE NEW POLE AT TOP OF PROPOSED SLOPE AND REMOVE EXISTING POLE.

CENTURYLINK TO PROVIDE NEW BURIED TELEPHONE CABLES

LEGEND:

PROP U/G (FO) CATV CABLES	TWC RELOC
PROP U/G TEL & FO CABLES	CENTURYLINK FOC RELOC
PROP U/G TEL CABLES	CENTURYLINK TEL RELOC
4" GAS	PIEDMONT NG RELOC
4" WL	CAMPBELL WL RELOC
12" SS	CAMPELL SEWER RELOC
PROP U/G POW CABLES	DUKE POWER RELOC

REVISIONS

8/17/99

SYSTIME = 09:09:09
FILENAME = DRAWING