J:\W-5206AG\Roadway\XSC

PROJ. REFERENCE NO.	SHEET NO.
W-5206AG	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Borrow excavation, shoulder borrow, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station CULVERT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+50.00	0	0	13+80.00	0	0												
24+00.00	16	12	14+00.00	29	0												
24+50.00	14	16	14+20.00	61	0												
25+00.00	10	26	14+40.00	104	0												
25+50.00	7	41	14+60.00	152	0												
26+00.00	5	65	14+80.00	213	0												
26+48.68	10	76	15+00.00	279	0												
26+88.11	11	57	15+20.00	342	0												
27+47.26	9	78	15+40.00	400	0												
27+95.52	0	56	15+60.00	518	0												
28+00.00	0	3	15+80.00	649	0												
28+03.29	0	3	16+00.00	737	0												
28+50.00	5	60	SKIP STATION RANGE 16+10.63 TO 17+26.66														
28+59.76	2	10	17+40.00	1029	0												
28+68.55	2	8	17+60.00	813	0												
29+04.20	10	19	17+80.00	631	0												
29+50.00	19	8	18+00.00	530	0												
30+00.00	24	5	18+20.00	435	0												
30+50.00	22	4	18+40.00	341	0												
			18+60.00	264	0												
			18+80.00	202	0												
			19+00.00	148	0												
			19+20.00	94	0												
			19+40.00	54	0												
			19+60.00	25	0												
			19+80.00	14	0												