PROJECT REFERENCE NO.	SHEET NO.
U-5305	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-Y2-	23+50	25+00	LT	75
5	-Y1-	12+50	15+50	RT	245
5	-Y1-	13+50	14+00	LT	35
			SUBTOTAL		355
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					4500
			TOTAL		4855
			SAY		5000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	10+00	11+50	LT	105
4	-L-	10+50	11+50	RT	60
			SUBTOTAL		165
		ADDITIONAL PSRM TO BE INSTALLED			125
			TOTAL		290
			SAY		300