



NOTE:

STAGING OF LATEX MODIFIED CONCRETE (LMC) OVERLAY-VERY EARLY STRENGTH IS NOT INDICATED ON STRUCTURE PLANS. IN THE EVENT STAGED CONSTRUCTION IS UTILIZED OR IF LONGITUDINAL JOINTS ARE NECESSARY, LONGITUDINAL CONSTRUCTION JOINTS OF LMC-VES SHALL BE LOCATED ALONG CENTERLINE OR EDGE OF TRAVEL LANES. WHEN PREPARING THE SURFACE FOR LMC OVERLAY ADJACENT TO A PREVIOUSLY PLACED LMC STAGE, THE PREVIOUSLY PLACED LMC SHALL BE REMOVED FOR A DISTANCE OF 4-INCHES FROM THE LMC EDGE. THE SURFACE OF THE NEW STAGE AREA, ALONG WITH THE 4 INCH OVERLAY AREA, SHALL BE PREPARED AS PER THE OVERLAY SURFACE PREPARATION SPECIAL PROVISIONS. NEW LMC SHALL BE PLACED IN THE 4-INCH OVERLAP, AS PART OF NEW LMC STAGE PLACEMENT.



TYPICAL SECTION



SECTION THRU DECK

STAGED LMC OVERLAY JOINT

(AS NEEDED)

PROJECT NO. I-5308
ROBESON COUNTY
 BRIDGE NO. 146

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

TYPICAL SECTION &
 LATEX MODIFIED
 CONCRETE DETAILS



DRAWN BY : M. WELDON DATE : 4/2014
 CHECKED BY : F. ASEFNIA DATE : 4/2014

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			S-18
2			4			23