PROJECT REFERENCE NO.	SHEET NO.
R-3622B	EC-3

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5&6	L	30+00	37+00	RT	1965
6	L	38+50	40+00	RT	210
6	L	41+50	44+00	RT	330
6&7	L	45+50	52+00	RT	1140
7	L	51+00	52+00	LT	115
7	L	56+00	59+00	LT	315
				SUBTOTAL	4075
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					54,925
				TOTAL	59,000
				SAY	65,000

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
8	L	61+00	63+00	RT	980
8	L	63+00	70+50	RT	1225
9&10	L	79+00	92+00	RT	980
10	L	92+00	94+00	RT	210
8	L	65+50	72+00	LT	1080
9	L	78+00	87+00	LT	1760
10	L	93+00	93+50	LT	160
				SUBTOTAL	6395
		ADDITIONAL PSRM TO BE INSTALLED			1155
				TOTAL	7550
				SAY	7700