

|                                         |                           |
|-----------------------------------------|---------------------------|
| PROJECT REFERENCE NO.<br><i>R-3622B</i> | SHEET NO.<br><i>EC-3A</i> |
| RW SHEET NO.                            |                           |
| ROADWAY DESIGN ENGINEER                 | HYDRAULICS ENGINEER       |

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

***SOIL STABILIZATION TIMEFRAMES***

| <i>SITE DESCRIPTION</i>                      | <i>STABILIZATION TIME</i> | <i>TIMEFRAME EXCEPTIONS</i>                                                            |
|----------------------------------------------|---------------------------|----------------------------------------------------------------------------------------|
| PERIMETER DIKES, SWALES, DITCHES, AND SLOPES | 7 DAYS                    | NONE                                                                                   |
| HIGH QUALITY WATER (HQW) ZONES               | 7 DAYS                    | NONE                                                                                   |
| SLOPES STEEPER THAN 3:1                      | 7 DAYS                    | IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED. |
| SLOPES 3:1 OR FLATTER                        | 14 DAYS                   | 7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.                                          |
| ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1 | 14 DAYS                   | NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.                                             |