# This electronic collection of documents is provided for the convenience of the user and is Not a Certified Document –

The documents contained herein were originally issued and sealed by the individuals whose names and license numbers appear on each page, on the dates appearing with their signature on that page.

This file or an individual page shall not be considered a certified document.

EROSION AND SEDIMENT CONTROL MEASURES STATE PROJECT REFERENCE NO. R=3622B Description STATE OF NORTH CAROLINA 1630.03 Temporary Silt Ditch DESCRIPTION Temporary Diversion. Temporary Silt Fence... Special Sediment Control Fence DIVISION OF HIGHWAYS 1622.01 Temporary Berms and Slope Drains Silt Basin Type B. Temporary Rock Silt Check Type-A. Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM) PLAN FOR PROPOSED THIS PROJECT CONTAINS EROSION CONTROL PLANS 1633.02 Temporary Rock Silt Check Type-B... HIGHWAY EROSION CONTROL Wattle / Coir Fiber Wattle. FOR CLEARING AND GRUBBING PHASE OF Wattle / Coir Fiber Wattle with Polyacrylamide (PAM) CONSTRUCTION. Temporary Rock Sediment Dam Type-A. Temporary Rock Sediment Dam Type-B.... TOTAL DISTURBED AREA = 517,492 SQ. FT.Rock Pipe Inlet Sediment Trap Type-A CHEROKEE COUNTY = 11.88 ACRESRock Pipe Inlet Sediment Trap Type-B. Stilling Basin . CLEARING LIMIT SHALL BE PERFORMED BY THE LIMITS ESTABLISHED BY METHOD II Special Stilling Basin. THIS PROJECT IS NOT WITHIN ANY MUNICIPAL BOUNDARIES Rock Inlet Sediment Trap: Type A. 1632.01LOCATION: NC 294 FROM SR 1130 (SUNNY POINT ROAD) 1632.02 Туре В. TO SR 1312 (UPPER BEAR PAW ROAD) 1632.03Type C. TYPE OF WORK: GRADING, DRAINAGE, PAVING AND STRUCTURES Skimmer Basin Tiered Skimmer Basin. Infiltration Basin BEGIN CONSTRUCTION
-DR1- STA. 10+10.00 BEGIN CONSTRUCTION END TIP PROJECT R-3622B BEGIN CONSTRUCTION
-DR2- STA. 10+10.00 -Y1-STA. 10+00.00-L-STA. 127 + 25.00BEGIN CONSTRUCTION
-Y4- STA. 10+00.00 END CULVERT -L- STA. 96 + 89.48 BEGIN CONSTRUCTION  $\sqrt{-DR3}$  STA. 10 + 25.00BEGIN CONSTRUCTION –DR5– STA. 10+00.00 BEGIN TIP PROJECT R-3622B -L-STA.11+35.007 END CONSTRUCTION
-Y5- STA. 11+25.00 END CONSTRUCTION END CONSTRUCTION -DR4-STA. 12 + 65.91-DR6-STA. 12 + 00.00END CONSTRUCTION END CONSTRUCTION/ -Y3- STA. 15+65.00 -Y2- STA. 12 + 15.00 BEGIN CONSTRUCTION / -DR7- STA. 10+50.00

GRAPHIC SCALE

....

**PLANS** 

PROFILE (HORIZONTAL)

PROFILE (VERTICAL)

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011 AND ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER RESOURCES.

Prepared in the Office of:

# VAUGHN & MELTON 1318F PATTON AVENUE

ASHEVILLE, NC 28806

2012 STANDARD SPECIFICATIONS

Designed by:

MICHAEL CLARK

*3376* 

LEVEL III CERTIFICATION NO.

JENNIFER PARISH, EI

Reviewed in the Office of:

# ROADSIDE ENVIRONMENTAL UNIT

1 South Wilmington St. Raleigh, NC 27611

2012 STANDARD SPECIFICATIONS

Reviewed by:

Roadway Standard Drawings

1631.01 Matting Installation

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revison thereto are applicable to this project and by reference hereby are considered a part of

1604.01 Railroad Erosion Control Detail 1605.01 Temporary Silt Fence 1607.01 Gravel Construction Entrance

1606.01 Special Sediment Control Fence 1622.01 Temporary Berms and Slope Drains

1630.01 Riser Basin 1630.02 Silt Basin Type B 1630.03 Temporary Silt Ditch

1630.04 Stilling Basin 1630.05 Temporary Diversion 1630.06 Special Stilling Basin

1632.01 Rock Inlet Sediment Trap Type A 1632.02 Rock Inlet Sediment Trap Type B 1632.03 Rock Inlet Sediment Trap Type C 1633.01 Temporary Rock Silt Check Type A 1633.02 Temporary Rock Silt Check Type B 1634.01 Temporary Rock Sediment Dam Type A 1634.02 Temporary Rock Sediment Dam Type B
1635.01 Rock Pipe Inlet Sediment Trap Type A
1635.02 Rock Pipe Inlet Sediment Trap Type B

1640.01 Coir Fiber Baffle 1645.01 Temporary Stream Crossing

# WATTLE WITH POLYACRYLAMIDE (PAM) DETAIL


PROJECT REFERENCE NO.


R-3622B

RW SHEET NO.

ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER





### NOTES:

USE MINIMUM 12 IN. DIAMETER EXCELSIOR WATTLE.

USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.

ONLY INSTALL WATTLE(S) TO A HEIGHT IN DITCH SO FLOW WILL NOT WASH AROUND WATTLE AND SCOUR DITCH SLOPES AND AS DIRECTED.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.


PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.


INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.

INSTALL MATTING IN ACCORDANCE WITH SECTION 1631 OF THE STANDARD SPECIFICATIONS.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH WATTLE.

INITIALLY APPLY 2 OUNCES OF ANIONIC OR NEUTRALLY CHARGED PAM OVER WATTLE WHERE WATER WILL FLOW AND 1 OUNCE OF PAM ON MATTING ON EACH SIDE OF WATTLE. REAPPLY PAM AFTER EVERY RAINFALL EVENT THAT IS EQUAL TO OR EXCEEDS 0.50 IN.







TOP VIEW

PROJECT REFERENCE NO	SHEET NO.	
R-3622B	EC-2A	
R/W SHEET N	10.	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER

# TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM) DETAIL






NOTES:

INSTALL TEMPORARY ROCK SILT CHECK TYPE A IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1633.01.

USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.


PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.


INITIALLY APPLY 4 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.




# SKIMMER BASIN WITH BAFFLES DETAIL

PROJECT REFERENCE NO	D. SHEET NO.
R-3622B	EC-2B
R/W SHEET N	<b>10</b> .
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER








COIR FIBER MAT ANCHOR OPTIONS

# NOTES

- 1. SEED AND PLACE MATTING FOR EROSION CONTROL ON INTERIOR AND EXTERIOR SIDESLOPES.
- 2. LIMIT EARTH DIKE HEIGHT TO 5 FT.

- 3. FOR BASIN DEPTH OF 3 FT., THE MINIMUM BASIN WIDTH SHALL BE 9 FT. 4. DETERMINE PRIMARY SPILLWAY WEIR LENGTH (FT.) USING Q/O.4, WHERE Q IS FLOW RATE (CFS) INTO BASIN. 5. PLASTIC SLOPE DRAIN PIPE AT INLET OF BASIN MAY BE REPLACED BY FILTRATION GEOTEXTILE OR TARP AS DIRECTED.
- 6. SOIL STABILIZATION GEOTEXTILE FOR PRIMARY SPILLWAY SHALL BE ONE CONTINUOUS PIECE OF MATERIAL OR OVERLAPPED 18 IN. (MIN.).

NOT TO SCALE



PROJECT REFERENCE NO.

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

# SOIL STABILIZATION SUMMARY SHEET

# MATTING FOR EROSION CONTROL PERMANENT SOIL REINFORCEMENT MAT


Company   Comp										
6 L 38+50 40+00 RT 210 8 L 63+00 70+50 RT 1225 6 L 41+50 44+00 RT 330 9¢10 L 79+00 92+00 RT 980 6¢7 L 45+50 52+00 RT 1140 10 L 92+00 94+00 RT 210 7 L 51+00 52+00 LT 115 6 L 65+50 72+00 LT 1080 7 L 56+00 59+00 LT 315 9 L 76+00 87+00 LT 1760 10 L 93+00 93+50 LT 160  MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER 54,925 TOTAL 59,000	CONST SHEET NO.	LINE		TO STATION	SIDE	ESTIMATE (SY)	CONST SHEET NO.	LINE		ESTIMATE (SY)
6 L 41+50 44+00 RT 330 9610 L 79+00 92+00 RT 980 667 L 45+50 52+00 RT 1140 10 L 92+00 94+00 RT 210 7 L 51+00 52+00 LT 115 8 L 65+50 72+00 LT 1080 7 L 56+00 59+00 LT 315 9 L 78+00 87+00 LT 1760 10 L 93+00 93+50 LT 160 10 L 93+00 93+50 LT 160 10 L 93+00 87+00 LT 155 TOTAL 59,000	5\$6		30+00	37+00	RT	1965	8		61+00 63+00 RT	980
6\$7   L   45+50   52+00   RT   1140   10   L   92+00   94+00   RT   210     7	6		38+50	40+00	RT	210	8		63+00 70+50 RT	1225
6\$7   L   45+50   52+00   RT   1140   10   L   92+00   94+00   RT   210   105   10	6		41+50	44+00	RT	330	9\$10		79+00 92+00 RT	980
7 L 56+00 59+00 LT 315 9 L 78+00 87+00 LT 1760 10 L 93+00 93+50 LT 160  6UBTOTAL 4075 MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER 54,925 TOTAL 59,000  TOTAL 7550	6\$7		45+50	52+00	RT	1140	10		92+00 94+00 RT	
10   10   93+00   93+50   LT   160   100	7		51+00	52+00	LT	115	8		65+50 72+00 LT	1080
SUBTOTAL   4075   SUBTOTAL   6395     MISCELLANEOUS MATTING 10 BE INSTALLED AS DIRECTED BY THE ENGINEER   54,925   ADDITIONAL PERM 10 BE INSTALLED   1155     TOTAL   59,000   TOTAL   7550	7		56+00	59+00	LT	315	9		78+00 87+00 LT	1760
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER 54,925  TOTAL 59,000  ADDITIONAL PERM TO BE INSTALLED TOTAL 7550							10		93+00 93+50 LT	160
101AL 59,000 101AL 7550				SUB	TOTAL	4075			SUBTOTAL	6395
	MISCELLANEC	OUS MATTING TO BE INSTA	ILLED AS DIRE	ECTED BY THE E	ENGINEER	54,925			ADDITIONAL PSRM TO BE INSTALLED	1155
9AY 65,000 9AY 7/00					TOTAL	59,000			TOTAL	7550
					SAY	65,000			SAY	7700


PROJECT REFERENCE NO	SHEET NO.		
R-3622B	EC-3A		
R/W SHEET N	10.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER		


# STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS


# SOIL STABILIZATION TIMEFRAMES


SITE DESCRIPTION	STAB/L/ZAT/ON T/ME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES, AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

















# PHASE 1:


- 1. INSTALL PERIMETER EROSION CONTROL DEVICES PRIOR TO CONSTRUCTION AS SHOWN IN THE CLEAR AND GRUBBING PHASE.
- 2. SHIFT TRAFFIC TO ONE LANE, TWO WAY PATTERN ON THE DOWNSTREAM SIDE OF THE PROPOSED CULVERT.
- 3. EXTEND 60" CMP APPROXIMATELY 24 LF AND CONSTRUCT IMPERVIOUS DIKE A TO DIVERT THE STREAM AROUND THE CONSTRUCTION.
- 4. CONSTRUCT UPSTREAM SIDE OF CULVERT AND PROPOSED CHANNEL IMPROVEMENTS.
- 5. PLACE FLOWABLE FILL IN THE EAST BARREL OF THE EXISTING 60" CMP.
- 6. CONSTRUCT A PORTION OF THE PROPOSED ROADWAY SUFFICIENT TO ALLOW TRAFFIC THROUGH THE SITE AS DESCRIBED IN THE TRAFFIC CONTROL PHASING.

### PHASE 2:

- 1. SHIFT TRAFFIC TO ONE LANE, TWO WAY PATTERN ON THE UPSTREAM SIDE OF THE PROPOSED CULVERT.
- 2. CONSTRUCT DOWNSTREAM SIDE OF CULVERT AND ANY NECESSARY OUTLET CHANNEL IMPROVEMENTS.
- 3. CONSTRUCT A PORTION OF THE PROPOSED ROADWAY SUFFICIENT TO ALLOW TRAFFIC THROUGH THE SITE AS DESCRIBED IN THE TRAFFIC CONTROL PHASING.

# **NOTES:**

- 1. CULVERT CONSTRUCTION SHALL BE PERFORMED IN ONLY DRY OR ISOLATED SECTIONS OF CHANNEL.
- 2. IMPERVIOUS DIKES ARE TO BE USED TO ISOLATE WORK FROM STREAM FLOW AS NECESSARY.
- 3. ALL GRADED AREAS SHALL BE STABILIZED WITHIN 24 HOURS.
- 4. MAINTENANCE OF STREAM FLOW OPERATIONS SHALL BE INCIDENTAL TO THE WORK. THIS INCLUDES POLETHYLENE SHEETING, DIVERSION PIPES, PUMPS AND HOSES.
- 5. THE CONTRACTOR SHALL NOT PUMP SEDIMENT-LADEN WATER DIRECTLY INTO STREAM. FOR DE-WATERING OF CULVERT SITES, THE CONTRACTOR SHALL FILTER SEDIMENT-LADEN WATER THROUGH SPECIAL STILLING BASIN. LOCATION OF THE SPECIAL STILLING BASIN TO BE APPROVED BY THE ENGINEER.





Asheville,

828 · 253 · 2796

■ North Carolina


Tennessee 423 • 467 • 8401 Knoxville, Tennessee 865 •546 •5800 □ Kentucky


Middlesboro, 606 • 248 • 6600

Spartanbura. ☐ South Carolina

Charlotte,
□ North Carolina C-II/CONS R-3622B 704 • 357 • 0488 R/W SHEET NO. Tri-Cities, **ROADWAY DESIGN HYDRAULICS** ENGINEER **ENGINEER** 864.574 4775 Copyright@ 1994 Vaughn & Melton, Inc. All Rights Reserved

PROJECT REFERENCE NO.





# PHASE 3:


- 1. SHIFT TRAFFIC TO ONE LANE, TWO WAY PATTERN ON THE DOWNSTREAM SIDE OF THE PROPOSED CLUVERT.
- 2. REMOVE IMPERVIOUS DIKE A AND CONSTRUCT IMPERVIOUS DIKE B TO FORCE STREAM FLOW THROUGH NEWLY CONSTRUCTED LOW FLOW BARREL.
- 3. REMOVE APPROXIMATELY 10 LF OF THE 60" CMP EXTENSION FOR THE CONSTRUCTION OF THE WING WALL.


### PHASE 4:

- 1. PLACE FLOWABLE FILL INTO EXISTING 60" CULVERT AND REMAINING 60" CMP EXTENSION AND BACKFILL.
- 2. REMOVE IMPERVIOUS DIKE B AND REMOVE TRAFFIC CONTROL TO ALLOW TWO WAY PATTERN THROUGH PROPOSED ROADWAY.

### **NOTES:**

- 1. CULVERT CONSTRUCTION SHALL BE PERFORMED IN ONLY DRY OR ISOLATED SECTIONS OF CHANNEL.
- 2. IMPERVIOUS DIKES ARE TO BE USED TO ISOLATE WORK FROM STREAM FLOW AS NECESSARY.
- 3. ALL GRADED AREAS SHALL BE STABILIZED WITHIN 24 HOURS.
- 4. MAINTENANCE OF STREAM FLOW OPERATIONS SHALL BE INCIDENTAL TO THE WORK. THIS INCLUDES POLETHYLENE SHEETING, DIVERSION PIPES, PUMPS AND HOSES, REMOVAL OF PIPING AND FLOWABLE FILL TO FILL EXISTING PIPES.
- 5. ONCE CONSTRUCTION OF CULVERT IS COMPLETE AND GROUND COVER IS STABILIZED, REMOVE EROSION CONTROL MEASURES ACCORDINGLY.





# PHASE 4

PLACE FLOWABLE FILL INTO REMAINING 60" CMP AND BACKFILL

