PROJECT NO.	SHEET NO.	TOTAL NO.
6CR.10431.83, 6CR.20431.83	27	
6CR.20261.83,		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4399000000-N TEMPORARY TRAFFIC CONTROL LS	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4721000000-E THERMO MSG ONLY 120 M EA	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E MERGE ARROW (90 MILS) EA	4725000000-E SHARKS TEETH (90 MILS) EA	4725000000-E THERMO LT STR RT ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4820000000-E 8" YELLOW PAINT LF	4835000000-E 24" WHITE PAINT LF	4900000000-N CRYSTAL & RED MARKERS EA	4900000000-N YELLOW & YELLOW MARKERS EA
6CR.20431.83	Harnett	31	SR1572	FROM: SR 1571 MP 0.0 TO: END MAINTENANCE MP 0.14	1	2	2WU	0.14	18																														
TOTAL FOR MAP NO. 31								**0.14**																															
6CR.20431.83	Harnett	32	SR 1580	FROM: SR 1532 MP 0.0 TO: DEAD END MP 0.11	1	2	2WU	0.11	18																														
TOTAL FOR MAP NO. 32								**0.11**																															
6CR.20431.83	Harnett	33	SR 2000 A	FROM: US HWY 421 MP 0.0 TO: END 4-LANE MP 0.08	6	2	MU	0.08	46					200	1,000					25				2	2			1									10	8
TOTAL FOR MAP NO. 33								**0.08**						**200**	**1,000**					**25**				**2**	**2**			**1**									**10**	**8**
6CR.20431.83	Harnett	34	SR 2000 B	FROM: END 4-LANE MP 0.08 TO: END C&G MP 0.26	8	2	2WU	0.18	24						2,400	150												2					2,400					20
TOTAL FOR MAP NO. 34								**0.18**							**2,400**	**150**												**2**					**2,400**					**20**
6CR.20431.83	Harnett	35	SR 2001	FROM: SR 2068 MP 0.0 TO: SR 2054 MP 0.35	1	2	2WU	0.35	18																														
TOTAL FOR MAP NO. 35								**0.35**																															
6CR.20431.83	Harnett	36	SR 2054	FROM: SR 2084 MP 0.0 TO: US HWY 421 MP 0.56	1	2	2WU	0.56	20							70		200							2					5		11,600	11,700	950			60	60
TOTAL FOR MAP NO. 36								**0.56**								**70**		**200**							**2**					**5**		**11,600**	**11,700**	**950**			**60**	**60**
6CR.20431.83	Harnett	37	SR 2057	FROM: SR 2000 MP 0.0 TO: DEAD END MP 0.08	1	2	2WU	0.08	18																														
TOTAL FOR MAP NO. 37								**0.08**																															
6CR.20431.83	Harnett	38	SR 2062	FROM: SR 2084 MP 0.0 TO: SR 2068 MP 0.11	8	2	2WU	0.11	30			600	200		2,300			200							1								2,300					20
TOTAL FOR MAP NO. 38								**0.11**				**600**	**200**		**2,300**			**200**							**1**								**2,300**					**20**
6CR.20431.83	Harnett	39	SR 2068	FROM: SR 2062 MP 0.08 TO: SR 2054 MP 0.22	1	2	2WU	0.14	20																														
TOTAL FOR MAP NO. 39								**0.14**																															
6CR.20431.83	Harnett	40	SR 2071	FROM: SR 2084 MP 0.0 TO: DEAD END MP 0.17	1	2	2WU	0.17	30																														
TOTAL FOR MAP NO. 40								**0.17**																															
6CR.20431.83	Harnett	41	SR 2081	FROM: NC HWY 210 MP 0.0 TO: DEAD END MP 0.32	10	2	2WU	0.32	20																														
TOTAL FOR MAP NO. 41								**0.32**																															
6CR.20431.83	Harnett	42	SR 2084 A	FROM: US HWY 421 MP 0.0 TO: BEGIN C&G (BOTH SIDES) MP 0.25	7	2	MU	0.25	36			1,500		80	3,300	70	200							10													25	30
TOTAL FOR MAP NO. 42								**0.25**				**1,500**		**80**	**3,300**	**70**	**200**							**10**													**25**	**30**
6CR.20431.83	Harnett	43	SR 2084 B	FROM: BEGIN C&G (BOTH SIDES) MP 0.25 TO: END 3-LANE MP 0.78	8	2	MU	0.53	40			800	2,200	330	5,600	520		1,600						15	10			6		30		330	7,800				15	85
TOTAL FOR MAP NO. 43								**0.53**				**800**	**2,200**	**330**	**5,600**	**520**		**1,600**						**15**	**10**			**6**		**30**		**330**	**7,800**				**15**	**85**
6CR.20431.83	Harnett	44	SR 2086	FROM: SR 2081 MP 0.0 TO: DEAD END MP 0.16	9	2	2WU	0.16	30																														
TOTAL FOR MAP NO. 44								**0.16**																															
6CR.20431.83	Harnett	45	SR 2172	FROM: SR 1184 MP 0.0 TO: END MAINTENANCE MP 0.20	1	2	2WU	0.2	20																														
TOTAL FOR MAP NO. 45								**0.2**																															
6CR.20431.83	Harnett	46	SR 2173	FROM: SR 1156 MP 0.0 TO: END MAINTENANCE MP 0.40	1	2	2WU	0.4	20																														
TOTAL FOR MAP NO. 46								**0.4**																															
6CR.20431.83	Harnett	47	SR 2174	FROM: SR 1156 MP 0.0 TO: END MAINTENANCE MP 0.31	1	2	2WU	0.31	20																														
TOTAL FOR MAP NO. 47								**0.31**																															
6CR.20431.83	Harnett	48	SR 2175	FROM: SR 1156 MP 0.0 TO: END MAINTENANCE MP 0.29	9	2	2WU	0.29	24																														
TOTAL FOR MAP NO. 48								**0.29**																															
TOTAL FOR PROJ NO. 6CR.20431.83								**19.63**		**1**	**2,199**	**38,900**	**2,400**	**610**	**49,160**	**810**	**200**	**2,000**		**40**				**27**	**15**			**9**		**35**		**205,930**	**199,440**	**950**			**110**	**468**
												41,300		**49,770**		**1,010**												**86**				**405,370**		**950**			**578**	
6CR.20261.83	Cumberland	49	SR 1006	FROM: US HWY 301 MP 0.0 TO: CAPE FEAR RIVER BRIDGE MP 0.32	5	2	MU	0.32	40	1	1,640			1,175	4,000					100				2		5		3			8	1,175	4,000			100	60	25
TOTAL FOR MAP NO. 49								**0.32**		**1**	**1,640**			**1,175**	**4,000**					**100**				**2**		**5**		**3**			**8**	**1,175**	**4,000**			**100**	**60**	**25**
6CR.20261.83	Cumberland	50	SR 1403	FROM: PAVEMENT JOINT @ SR 3569 MP 0.20 TO: BEGIN C&G AT SR 1400 MP 2.2	4	2	2WU	2	27			22,000		200	19,300	210																						155
TOTAL FOR MAP NO. 50								**2**				**22,000**		**200**	**19,300**	**210**																						**155**
6CR.20261.83	Cumberland	51	SR 1451	FROM: NC HWY 87 MP 2.36 TO: PVMT. JNT. @ HARLEY POPE STREET MP 3.71	2	2	2WU	1.35	23			14,400		370	14,360	490	200			60				3	2	2											51	111
TOTAL FOR MAP NO. 51								**1.35**				**14,400**		**370**	**14,360**	**490**	**200**			**60**				**3**	**2**	**2**											**51**	**111**
6CR.20261.83	Cumberland	52	SR 1721	FROM: SR 1720 MP 1.81 TO: SR 1728 MP 4.54	4	2	2WU	2.73	23										100	50		4										60,000	54,000					190
TOTAL FOR MAP NO. 52								**2.73**											**100**	**50**		**4**										**60,000**	**54,000**					**190**
6CR.20261.83	Cumberland	53	SR 1828	FROM: US HWY 301 MP 3.86 TO: SR 1831 MP 2.81	1	2	2WU	1.05	23																							22,800	20,520					75
TOTAL FOR MAP NO. 53								**1.05**																								**22,800**	**20,520**					**75**
6CR.20261.83	Cumberland	54	SR 1831	FROM: SR 1006 MP 0.0 TO: SR 1828 MP 4.08	1	2	2WU	4.08	23			44,000		450	41,150	280								6	4												28	317
TOTAL FOR MAP NO. 54								**4.08**				**44,000**		**450**	**41,150**	**280**								**6**	**4**												**28**	**317**
6CR.20261.83	Cumberland	55	SR 1832	FROM: SR 1831 MP 1.71 TO: SR 1838 MP 0.0	3	2	2WU	1.71	23															3	3							19,600	20,800	100	3,220		48	145
TOTAL FOR MAP NO. 55								**1.71**																**3**	**3**							**19,600**	**20,800**	**100**	**3,220**		**48**	**145**
6CR.20261.83	Cumberland	56	SR 2010	FROM: NC HWY 53 MP 3.48 TO: SR 2012 MP 0.91	3	2	2WU	2.57	22																							56,000	47,600					
TOTAL FOR MAP NO. 56								**2.57**																								**56,000**	**47,600**					
6CR.20261.83	Cumberland	57	SR 2274	FROM: SR 2220 MP 0.0 TO: NC HWY 59 MP 1.64	1	2	2WU	1.64	24																							36,000	30,600					
TOTAL FOR MAP NO. 57								**1.64**																								**36,000**	**30,600**					
TOTAL FOR PROJ NO. 6CR.20261.83								**17.45**		**1**	**1,640**	**80,400**		**2,195**	**78,810**	**980**	**200**		**100**	**210**		**4**		**14**	**9**	**7**		**3**			**8**	**195,575**	**177,520**	**100**	**3,220**	**100**	**187**	**1,018**
												80,400		**81,005**		**1,180**					**4**							**41**				**373,095**		**3,320**			**1,205**	
GRAND TOTAL								**61.82**		**3**	**6,783**	**351,900**	**36,400**	**35,715**	**337,180**	**10,925**	**3,500**	**2,000**	**100**	**1,270**	**24**	**8**	**4**	**285**	**98**	**9**	**4**	**59**	**9**	**35**	**8**	**446,915**	**410,960**	**1,050**	**3,220**	**100**	**2,186**	**3,633**
												388,300		**372,895**		**14,425**					**36**							**507**				**857,875**		**4,270**			**5,819**	