

## ELEVATION

## BLOCKOUT IN WING WALL

NOTE: THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE JOINT BETWEEN THE DECK AND THE APPROACH SLAB HAS BEEN SAWED AND THE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

END BENT #1 BAR | NO. | SIZE | TYPE | LENGTH | WEIGHT B2 **#**10 39'-7" **#**10 B3 #5 | STR | 39'-9" #5 | STR | 13'-0" #4 STR 21'-1" #4 STR 2'-10" #4 STR В8 #4 STR B9 | 21'-0" #4 STR 29'-8" #4 STR H1 | 20 | #5 | 3 #5 20 11'-0" 18 #5 Н3 11'-2" H4 | 18 | #5 | 4 16 | #4 | STR | 21'-1" 8 | #5 | STR | 3'-7" S1 | 22 | #4 | S2 20 **#**4 #4 1 9'-2" S3 | 42 | H4 9'-1" S4 | 20 | #4 U1 | 32 | #4 U2 | 15 | #4 V1 64 #5 STR 7'-4" V2 | 32 | #5 | STR | 10'-2" V3 | 28 | #5 | STR | 2'-10" 2'-10" REINFORCING STEEL ▲ CLASS "A" CONCRETE BREAKDOWN POUR #1 CAP & LOWER PART OF WINGS 24.3 C.Y. 2'-10" POUR #2 BACKWALL & UPPER PART 1′-8″Ø (8) CLASS "A" CONCRETE TOTAL 12"PRESTRESSED CONCRETE PILES NO. \_\_5\_ PILE REDRIVES

ALL BAR DIMENSIONS ARE OUT TO OUT.

-BAR TYPES

▲ THE CONCRETE DISPLACED BY THE 12"PRESTRESSED CONCRETE PILES HAS BEEN DEDUCTED FROM THE QUANTITY OF CLASS 'A' CONCRETE FOR THE END BENT CAP.

> PROJECT NO. R-2514B ONSLOW & JONES COUNTY STATION: 116+07.49 -L-

BILL OF MATERIAL

3

4

730

386

535

249

27

113

25

14

15

15

15

247

250

188

186

225

30

174

145

101

87

132

58

490

339

263

LBS. 5039

34.3 C.Y.

<u>3</u> EA.

42'-5"

22′-5″

31′-1"

7′-1"

7′-3"

7′-5″

7'-7"

11'-10"

12'-0"

10'-0"

9'-11"

11'-10"

10'-10"

3'-7"

6′-6″

6'-2"

5′-10″


9'-0"


LIN.FT. 250

SHEET 3 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

> SUBSTRUCTURE END BENT No. 1





BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

## TEMPORARY DRAINAGE AT END BENT

DRAWN BY :	K.P. SEDAI, P.E.		DATE: 6/16/14
CHECKED BY :	M.D. PISO		DATE: 8/11/14
DESIGN ENGINEER	OF RECORD:	E.K. POPE	DATE : 1/21/15

SEAL (

\* NOINEER

Tim Coggins

- DEFD4A8D48FA47B 3/26/2015