

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

**SHOULDER BERM  
 GUTTER SUMMARY**

SURVEY LINE	LOC.	STATION	STATION	LENGTH
-L-	LT	87 + 40.00	101 + 20.83	1380.83
-L-	RT	99 + 45.00	101 + 20.83	175.83
-L-	LT	102 + 89.17	116 + 27.00	1337.83
-L-	RT	102 + 89.17	117 + 95.00	1505.83
TOTAL:				4400.32
SAY:				4450

**ASPHALT PAVEMENT  
 REMOVAL SUMMARY**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD <sup>2</sup>
-EL-	15 + 23.71	30 + 24.15	LT/RT	4668.04
-L-	101 + 20.00	102 + 90.00	LT	528.89
-L-	167 + 00.00	176 + 00.00	LT	2800.00
-EL-	209 + 81.42	-Y- 24 + 47.69	LT/RT	4067.62
-Y1-	14 + 11.43	18 + 29.30	LT/RT	835.74
-Y1-	22 + 00.00	-Y- 38 + 93.75	LT/RT	1629.12
-Y2-	14 + 84.71	19 + 55.00	LT/RT	1045.09
-DET3-	16 + 00.00	32 + 26.00	LT/RT	4352.22
-DET4-	12 + 50.00	18 + 22.00	LT/RT	1356.67
-DET5-	17 + 40.00	25 + 25.00	LT/RT	703.33
-L-	13 + 90.00	16 + 40.00	LT/RT	344.44
TOTAL:				22331.16
SAY:				23000

**SUMMARY OF BREAKING  
 EXISTING ASPHALT PAVEMENT**

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD <sup>2</sup>
-L-	26 + 50.00	101 + 20.00	LT	23240.00
-L-	102 + 90.00	167 + 00.00	LT	19942.22
-L-	176 + 00.00	206 + 65.00	LT	9535.56
TOTAL:				52717.78
SAY:				55000

5/28/99  
 3/18/2015  
 P:\862501\Cadd\2514C\_Roadway\Proj\2514C\_Rdy\_sum.dgn  
 thurman