

PROJECT NO.	SHEET NO.	TOTAL NO.
6CR.10781.83, 6CR.20781.83	13	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4685000000-E	4686000000-E			4695000000-E	4697000000-E	4705000000-E	4710000000-E	4721000000-E		4725000000-E		4810000000-E		4830000000-E	4835000000-E	4840000000-N	4900000000-N	
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	4" X 90 M WHITE THERMO LF	4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M YELLOW THERMO LF	8" X 120 M WHITE THERMO LF	16" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO RXR 120 M EA	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	4" WHITE PAINT LF	4" YELLOW PAINT LF	16" WHITE PAINT LF	24" WHITE PAINT LF	PAINT MSG RXR EA	CRYSTAL & RED MARKERS EA	YELLOW & YELLOW MARKERS EA	
6CR.10781.83	Robeson	1	US 501	US 301 MP 2.66 TO CANAL ST MP 2.96	3	4	MU	0.3	46	34		100	3,200			100	200	2		2	2	75	3,200	100	150	2	10	25		
		"	"	CANAL ST MP 2.96 TO SR 1141 MP 3.09	3	4	MU	0.13	36	15	1,200		1,600			150							1,600		150			15		
		"	"	SR 1141 MP 3.09 TO SR 1135 MP 5.41	2	2	2WU	2.3	26	261	26,000		22,100										8,500					75		
TOTAL FOR MAP NO. 1								2.73		310		27,200	100	26,900		100	350	2		2	2	75	13,300	100	300	2	10	115		
6CR.10781.83	Robeson	2	NC 130	US 74 MP 0.88 TO SR 2225 MP 3.28	2	2	2WU	2.4	24	272	26,000		22,100			100			6										175	
TOTAL FOR MAP NO. 2								2.4		272	26,000		22,100		100		6												175	
6CR.10781.83	Robeson	3	NC 130	CJ W OF I-95 MP 21.45 TO SR 2518 MP 22.23	2	2	2WU	0.78	24	89	7,000		6,000																60	
		"	"	SR 2518 MP 22.23 TO US 501 MP 22.65	3	3	MU	0.42	44	48		150	4,500			50			2	2	150	4,500					10	30		
TOTAL FOR MAP NO. 3								1.2		137	7,000	150	4,500		50		2	2	150	4,500							10	90		
6CR.10781.83	Robeson	4	NC 710	NC 711 MP 10.77 TO SR 1340 13.37	2	2	2WU	2.6	24	295	28,000		23,800			100	150	4											180	
TOTAL FOR MAP NO. 4								2.6		295	28,000		23,800		100	150	4												180	
6CR.10781.83	Robeson	5	NC 710	SR 1345 MP 15.7 TO NC 72 MP 18.6	2	2	2WU	2.9	24	329	31,500		26,775																205	
TOTAL FOR MAP NO. 5								2.9		329	31,500		26,775																205	
TOTAL FOR PROJ NO. 6CR.10781.83								11.83		1,343	119,700	250	110,075		200	650	6	6	4	4	225	17,800	100	300	2	20	765			
										110,325			12		8		18,025		785											
6CR.20781.83	Robeson	6	SR 1002	SR 2100 MP 6.2 TO SR 2121 MP 8.6	1	2	2WU	2.4	22	272	0.10	26,500		22,525															170	
TOTAL FOR MAP NO. 6								2.4		272	0.10	26,500		22,525															170	
6CR.20781.83	Robeson	7	SR 1107	SCOTLAND CL MP 0.0 TO NC 83 MP 3.09	1	2	2WU	3.09	22	351	0.10											65,400	55,590							
		"	"	NC 83 MP 3.09 TO US 301 MP 4.74	4	2	2WU	1.65	24	187	0.10											36,000	30,600							
TOTAL FOR MAP NO. 7								4.74		538	0.20											101,400	86,190							
6CR.20781.83	Robeson	8	SR 1111	SCOTLAND CL MP 0.0 TO WCL MAXTON MP 0.49	1	2	2WU	0.49	20	56	0.10											11,200	9,520							
		"	"	WCL MAXTON MP 0.49 TO SR 1108 MP 0.69	1	2	2WU	0.2	24	23	0.10											3,200	3,200					13		
TOTAL FOR MAP NO. 8								0.69		79	0.20											14,400	12,720					13		
6CR.20781.83	Robeson	9	SR 1320	HOKE CL MP 0.0 TO NC 71 MP 2.67	5	2	2WU	2.67	22	303	0.10											56,000	47,600							
TOTAL FOR MAP NO. 9								2.67		303	0.10											56,000	47,600							
6CR.20781.83	Robeson	10	SR 1340 CURVE WIDENING	NC 710 MP 4.54 TO BEG C&C MP 6.62	4	2	2WU	2.08	24	236	0.10			780					10			46,300	43,830			30	176			
TOTAL FOR MAP NO. 10								2.08		236	0.10			780					10			46,300	43,830			30	176			
6CR.20781.83	Robeson	11	SR 1373	US 74 MP 0.0 TO NC 710 MP 1.53	6	2	2WU	1.53	24	174	0.10											34,400	30,000					120		
TOTAL FOR MAP NO. 11								1.53		174	0.10											34,400	30,000					120		
6CR.20781.83	Robeson	12	SR 1505	SR 1001MP 0.0 TO NC 71 MP 2.02	4	2	MU	2.02	24	229	0.10											43,470	21,500					133		
TOTAL FOR MAP NO. 12								2.02		229	0.10											43,470	21,500					133		
6CR.20781.83	Robeson	13	SR 2413	LUMBERTON CL MP 3.05 TO NC 41 MP 3.61	1	2	2WU	0.56	24	64	0.10				100		40					14,000	12,000							
TOTAL FOR MAP NO. 13								0.56		64	0.10				100		40					14,000	12,000							
TOTAL FOR PROJ NO. 6CR.20781.83								16.69		1,895	1.00	26,500		22,525	780	100	200	690	6	6	14	4	309,970	253,840		30	612			
										22,525			10		563,810		642													
GRAND TOTAL								28.52		3,238	1.00	146,200	250	132,600	780	100	200	690	6	6	14	4	310,195	271,640	100	300	2	50	1,377	
										132,850			12		18		581,835		1,427											