STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT +%	BORROW	WASTE
PHASE I					
-L- RT 158+31.70 TO 188+00.00	426,032		5,262		420,770
-L- RT 188+00.00 TO 198+02.96 (BRIDGE)	102,181		2,626		99,555
-L- RT 199+35.84 (BRIDGE) TO 229+00.00	8,596		37,116	28,520	
-L- RT 229+00.00 TO 233+40.93(BRIDGE)			12,259	12,259	
SUBTOTAL	536,809		57,263	40,779	520,326
L- RT 234+74.46(BRIDGE) TO 241+33.23(BRIDGE)			14,429	14,429	
-L- RT 243+93.23(BRIDGE) TO 251+72.02	26		41,662	41,636	
-Y9- 10+35.50 TO 16+90.08	76,720		6		73,714
-Y10- 12+75.00 TO 17+62.15	11,545		902		10,643
SUBTOTAL	85,291		56,999	56,065	84,358
N/40 4/4 50 00			10		
-Y13- 11+50.00 TO 12+86.60	95		16		79
-Y13A- 10+21.98 TO 12+77.00	4,461				4,461
-DR1- 10+35.50 TO 15+43.00	31,426				31,426
-DR2- 10+35.50 TO 14+90.01	31,214				31,214
SUBTOTAL	67,196		16		67,179
-DR3- 10+35.50 TO 19+95.00	95,398		216		95,182
-DR3B- 10+06.00 TO 12+35.00	5,203		1		5,202
-DR5- 10+50.00 TO 11+55.00	423				423
-DET- RT 251+72.02 TO 261+05.51	42,918		421		42,497
SUBTOTAL	143,942		638		143,304
PHASE II					
-L- LT 158+31.70 TO 188+00.00	15,818		16,315	497	
-L- LT 188+00.00 TO 197+96.58 (BRIDGE)	12,570		1,588		10,982
-L- LT 199+23.81 (BRIDGE) TO 229+00.00	104,035		12,831		91,204
-L- LT 229+00.00 TO 233+64.04(BRIDGE)	272		713	441	
SUBTOTAL	132,695		31,447	938	102,186
L- LT 234+97.45 (BRIDGE) TO 241+41.61 (BRIDGE)	272		1,528	1,256	
-L- LT 244+01.61 (BRIDGE) TO 251+72.02			20,901	20,901	
-Y11- 10+55.00 TO 12+65.47	468		576	108	
-Y12- 12+85.00 TO 14+87.00	80		437	357	
-DET- LT 251+72.02 TO 261+05.51	7,849		1,884		5,965
SUBTOTAL	8,669		25,326	22,623	5,965
-DR4- 10+35.50 TO 13+24.54	7		2,615	2,608	
SUBTOTAL	7		2,615	2,608	
TOTAL	074.000		474.005	400.040	000 047
TOTAL	974,609		174,305	123,013	923,317
LOSS DUE TO CLEARING & GRUBBING	-20,000				-20,000
ROCK WASTE TO REPLACE BORROW	-20,000			01 170	
			16 006	-81,179	-81,179
ADJUST FOR ROCK WASTE			-16,236	-16,236	
ELIMINATE EARTH SHRINKAGE FACTOR FOR ROCK			-14,612	-14,612	40.005
WASTE IN LIEU OF BORROW	054.000		440.457	-10,985	-10,985
PROJECT TOTAL	954,609		143,457		811,152
EST 5% TO BEDI ACE TOD SOIL ON BORDOW DIT					
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT					
GRAND TOTAL	954,609		143,457		Q11 1E0
GNAND I O IAL	904,009		143,437		811,152
SAY	954,700				
5/11	337,700				
EST. DDE = 2820 CUBIC YARDS					
			1		

NOTE: Earthwork quantities are calculated by the Roadway Design Unit.
These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

NOTE: Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

CONTINGENCY ITEMS: GEOTECHNICAL REPORT - DESIGN AND CONSTRUCTION RECOMMENDATIONS DATED: SEPTEMBER 27, 2013

UNDERCUT CONTINGENCY = 200 CY
SHALLOW UNDERCUT CONTINGENCY = 500 CY
CLASS IV SUBGRADE STABILIZATION CONTINGENCY = 200 TONS
SELECT GRANULAR CONTINGENCY = 200 CY
PAVEMENT STRUCTURE VOLUME = 14,449 CY