STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF GEOTEXTILE FOR PAVEMENT STABILIZATION

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD^2
-L-	160+50	161+50	RT	467
-L-	185+00	186+25	LT	417
-L-	197+50	198+50	RT	444
-L-	228+00	234+00	RT	2,400
-L-	235+50	241+50	RT	2,667
-L-	244+00	249+50	RT	2,750
-L-	249+50	251+50	CL	2,889
			TOTAL:	12,034
			SAY:	12,034

SUMMARY OF SUBSURFACE DRAINAGE

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	DRAIN TYPE* UD/BD/SD	LF
CONTINGENCY				SD	1,000
				TOTAL LF:	1,000

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

SURVEY LINE	STATION	STATION	Aggregate Type ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS
-L-	CONTINGENCY		ASU		500	200	1200	
-L-	CONTINGENCY		AST	3				250
			TOTAL CY/TONS/SY:		500	200	1200	250

ASU = Aggregate Subgrade, AST = Aggregate Stabilization

* Total Square yards of Geotextile for Soil Stabilization is only the estimated quantity for ASU/AST and may only represent a portion of the geotextile quantity shown in the Item Sheets Proposal.

5/28/99
6/28/2005 2:28:28 PM
R2915B_Rdwy_SUM_3G-1.dgn
USER: thill