
+

BM #9: RR SPIKE IN ROOT OF 24"FORKED CHERRY TREE, N 932968, E 1262584, 130' LEFT, -L- STA. 215+49.00, EL. 2871.28



LOCATION SKETCH

## NOTES:

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE, PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

AT THE CONTRACTOR'S OPTION, AND UPON REMOVAL OF THE CAUSEWAY, THE CLASS II RIP RAP MAY BE PLACED AS RIP RAP SLOPE PROTECTION. SEE SPECIAL PROVISIONS FOR CONSTRUCTION MAINTENANCE AND REMOVAL OF TEMPORARY ACCESS AT STATION 242+67.42 -L-.

NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.

THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-5 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.

THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 40 FT.LEFT AND 12 FT.RIGHT OF BRIDGE WORK LINE AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

THE EXISTING STRUCTURE CONSISTING OF FOUR SPANS, 57'-6"FT. EACH, WITH A CLEAR ROADWAY OF 26'ON REINFORCED CONCRETE DECK GIRDERS ON END BENTS WITH REINFORCED CONCRETE CAPS ON TIMBER PILES & INTERIOR BENTS WITH REINFORCED CONCRETE POSTS AND BEAMS LOCATED AT THE PROPOSED STRUCTURE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY NOT POSTED.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18 - EVALUATING SCOUR AT BRIDGES".

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

## HYDRAULIC DATA

DESIGN DISCHARGE FREQUENCY OF DESIGN FLOOD DESIGN HIGH WATER ELEVATION DRAINAGE AREA BASE DISCHARGE (Q100)

BASE HIGH WATER ELEVATION

= 16,000 C.F.S. = 50 YRS.

= 2862.2 = 130 SQ. MI.

= 19,000 C.F.S.

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE FREQUENCY OF OVERTOPPING FLOOD OVERTOPPING FLOOD ELEVATION

= 24,000+ C.F.S. = 500+ YRS. = 2869.2

PROJECT NO. R-2915B

ASHE COUNTY

STATION: 242+67.42 -L-

SHEET 3 OF 3 REPLACES BRIDGE #10

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

BRIDGE OVER SOUTH FORK NEW RIVER ON US 221 BETWEEN SR 1103 AND SR 1169 SBL

SHEET NO REVISIONS S04-3 NO. BY: DATE: BY: DATE: SHEETS

	CONSTRUCTION, MAINTENANCE & REMOVAL OF TEMPEMPORARY ACCESS	REMOVAL OF EXISTING STRUCTURE	4'-0"Ø DRILLED PIERS IN SOIL	4'-0"Ø DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 4'-0"Ø DRILLED PIERS	4'-6"Ø DRILLED PIERS IN SOIL	4'-6"Ø DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 4'-6"Ø DRILLED PIERS	CSL TESTING	UNCLASSIFIED STRUCTURE EXCAVATION		
	LUMP SUM	LUMP SUM	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	EACH	LUMP SUM		
SUPERSTRUCTURE												
END BENT NO.1										LUMP SUM		
BENT NO.1			12.0	32.0	16.0							
BENT NO.2						19.2	39.0	10.0				
END BENT NO.2										LUMP SUM		
TOTAL	LUMP SUM	LUMP SUM	12.0	32.0	16.0	19.2	39.0	10.0	1	LUMP SUM		

	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	SPIRAL COLUMN REINFORCING STEEL	С	54" ESTRESSED ONCRETE GIRDERS	HP 12 X 53 STEEL PILES		CONCRETE BARRIER RAIL	RIP RAP CLASS II (2'-0"THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS
	SQ.FT.	SQ.FT.	CU. YDS.	LUMP SUM	LBS.	LBS.	NO.	LIN.FT.	NO.	LIN.FT.	LIN.FT.	TONS	SQ. YDS.	LUMP SUM
SUPERSTRUCTURE	9619	9555		LUMP SUM			12	1023			516.5			LUMP SUM
END BENT NO.1			31.6		4341				6	165		100	110	
BENT NO.1			35.0		9155	1943								
BENT NO.2			42.8		9963	2672								
END BENT NO.2			31.5		4289				8	280		176	195	
TOTAL	9619	9555	140.9	LUMP SUM	27748	4615	12	1023	14	445	516.5	276	305	LUMP SUM

DATE : 5/4/14 \_\_ DATE : \_\_7/31/14 CHECKED BY : R.F. WERTMAN DESIGN ENGINEER OF RECORD: R.F. WERTMAN DATE: 10/30/14 PLANS PREPARED BY: Suite 170 **Gannett Fleming** (919) 859-4880 Excellence Delivered As Promised NC Lic. No. F-0270