EMERGENCY VEHICLE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #2.


```
PREEMPTION #2 SETTINGS (NEXT:1-10)
GRN YEL RED | 12345678910111213141516
1 255 0.0 0.0 ;
2 0 0.0 0.0 ;
3 0 0.0 0.0 ;
4 0 0.0 0.0 ;
5 1 0.0 0.0 ¦ X
EXIT CALLS
           OPTIONS
PRIORITY (Y/N TO SELECT) .....MED
DELAY TIMER (0-255 SEC) ....*
MIN GREEN BEFORE PRE (O= DEFAULT)....1
PED CLEAR BEFORE PRE (O= DEFAULT)....O
YELLOW CLEAR BEFORE PRE (0= DEFAULT).0.0
RED CLEAR BEFORE PRE (O= DEFAULT)....O.O
DWELL MIN TIMER (0-255 SEC) ....*
DWELL MAX TIMER (0=OFF,1-255MIN) ....0
DWELL HOLD-OVER TIMER (0-255) .....0
LATCH CALL? .....Y
LINK TO NEXT PREEMPT? ......
ENABLE BACKUP PROTECTION? .....N
HOLD CLEAR 1 PHASES DURING DELAY? ... N
FAST GREEN FLASH DWELL PHASES? .....N
PED CLEARANCE THROUGH YELLOW? .....N
INHIBIT OVERLAP GREEN EXTENSION? ....N
SERVICE DURING SOFTWARE FLASH? .....N
REST IN RED DURING DWELL INTERVAL? ..Y
FLASH DWELL INTERVAL? ......
ALLOW PEDS IN DWELL INTERVAL? .....N
RE-TIME DWELL INTERVAL? .....Y
OVERLAPS:
                    | ABCDEFGHIJKLMNOP
DWELL INT FLASH YELLOW
OMIT OVERLAPS:
```

* Denotes timing to be determined in field.

LOGICAL I/O PROCESSOR PROGRAMMING DETAIL TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)

- 1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 3 THROUGH 5.
- 2. FROM MAIN MENU PRESS '6' (OUTPUTS). THEN '3' (LOGICAL I/O




LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

OUTPUT REFERENCE SCHEDULE OUTPUT 39 = Overlap D Red OUTPUT 40 = Overlap D Yellow OUTPUT 41 = Overlap D Green

OVERLAP PROGRAMMING DETAIL


(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS). THEN '1' (VEHICLE OVERLAP SETTINGS).



OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 03-1021 DESIGNED: March 2008 SEALED: June 19, 2008 REVISED: 7/20/2015



George C. Brown7/30/2015

SEAL

This document originally

issued and sealed by F. Royal Hinshaw, #032117,

on 8-12-08. This media shall

not be considered a


certified document.

PROJECT REFERENCE NO

W-5103A

Sig. 8.4

|Electrical Detail - Sheet 4 of 5



US 421 (Carolina Beach Road) The Kings Hwy. Division 3 New Hanover County Myrtle Grove LAN DATE: March 2008 REVIEWED BY:

REPARED BY: R Hinshaw REVISIONS INIT. DATE REVISED FIRE PREEMPTION PUSH BUTTON AND INDICATOR LAMP WIRING DETAIL. ALSO REVISED PREEMPT 2/6/09 PROGRAMMING DETAIL AND ADDED AC ISOLATOR DETAIL. MCB ,/30/2015 No change to Electrical Detail. CES 6/14/15

SIGNATURE SIG. INVENTORY NO. 03-1021

02/04/2009 -MWH-