COMPUTED BY: DBE DATE: 8-12-2014
CHECKED BY: RWP DATE: 06-24-2015

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
R-2603	3B-3

M A Engineering Consultants, Inc. NC License: F-0160
598 East Chatham Street Suite 137 Cary, NC 27511
Phone: 919.297.0220 Fax: 919.297.0221

SUMMARY OF SHOULDER BERM GUTTER

IN LINEAR FEET

STATION TO STATION	LOCATION	LF
-L- STA. 113+80.00 to 116+36.69	LT	256.7
-L- STA. 113+96.00 to 116+35.83	RT	239.8
-L- STA. 118+34.47 to 124+75.00	LT	640.5
-L- STA. 118+34.87 to 124+29.00	RT	594.1
-L- STA. 151+24.00 to 161+76.00	RT	1,052.0
	TOTAL	2,783.2
	SAY	2,784

SUMMARY OF ASPHALT PAVEMENT REMOVAL

IN SQUARE YARDS

LINE	BEG STATION	END STATION	LOCATION	SQUARE YARDS
-L-	15+89	18+49	MED	651
-Y1-	24+73	29+74	MED	944
-Y2-	18+25	18+71	LT	6
-Y2-	17+83	18+17	RT	11
-Y3-	10+72	10+76	CL	22
-Y4-	10+00	10+76	CL	283
-Y5-	10+72	10+75	CL	18
-Y6-	10+50	11+79	CL	559
-Y7-	11+71	END OF EX. LEGION DR.	LT	1238
-L-	56+88	60+10	MED	440
-Y8-	14+37	14+55	CL	140
-L-	62+17	63+71	RT	13
-L-	64+83	70+41	LT	129
-L-	66+24	69+32	RT	250
-L-	80+00	86+25	CL	1482
-Y9-	10+17	13+25	CL	338
-Y9DET-	10+10	14+00	CL	800
-Y10-	12+62	12+67	CL	18
-Y11-	13+59	13+63	CL	41
-L-	103+92	104+94	MED	15
-Y12-	BEGINNING	15+97	RT	1446
-L-	107+37	BRIDGE	RT	2263
-L-	BRIDGE	130+75	RT	3522
-L-	134+43	140+40	CL	648
-Y16-	11+05	END OF VISTA LN.	CL	1355
-Y16DET-	11+38	17+42	CL	1046
-Y17-	12+52	END OF BEAUMONT	RT	1422
-L-	174+28	176+97	RT	35
-L-	183+60	189+30	MED	672
-Y18-	23+18	24+20	MED	19
-Y18-	26+52	29+20	RT	129
-Y18-	29+38	29+91	RT	34
-Y18-	31+06	38+88	CL	2048
-Y19-	10+27	12+50	CL	485
-DRIVE1-	10+82	10+57	CL	95
Temporary Pavement (See Work Zone Traffic Control Plans for additional information)				
-L-	54+90.00	60+88.00	LT	372
-L-	56+88.50	60+10.00	MEF	477
-L-	81+13.00		(Y19 TURNOUT)	132
-L-	98+43.00		(DRIVE6 TURNOUT)	99
-L-	103+50.00	115+18.00	LT	2028
-L-	106+40.00		Y12 TURNOUT	139
-L-	121+68.00	131+50.00	LT	1251
-L-	146+44.00		Y16 TURNOUT	57
-L-	163+80.00		Y17 TURNOUT	118
-XOVR1-	11+97.97	17+88.43	CL	533
-XOVR2-	10+43.29	16+34.43	CL	482
			TOTAL	28,303
			SAY	28,400

SUMMARY OF WOVEN WIRE FENCE, 47" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC LF	4" POSTS EA	5" POSTS EA
-L- 60+50.00 RT to -L- 62+60.37 RT	RT	245	13	10
-L- 70+30.00 LT to -L- 73+10.00 LT	LT	322	16	13
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE.	TOTAL	567	29	23
	SAY	600	34	27

SUMMARY OF CHAIN LINK FENCE, 48" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC (LF)	FABRIC, VINYL COATED (LF)	LINE POSTS (EA)	TERMINAL POSTS (EA)
-Y1A- 28+76.00 to -Y1A- 29+10.00	LT	41		4	4
-Y1- 29+00.00 to -Y1- 29+42.00	RT	46		4	4
-L- 44+17.00 to -L- 44+35.00	RT	61		2	3
	TOTAL	148		14	11
	SAY	160		16	13

SUMMARY OF FENCE GATES, CHAIN LINK

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	SINGLE OR DOUBLE	HEIGHT x WIDTH x OPENING (IN)	GATES (EA)	METAL GATE POSTS (EA)
-L- 44+17.00 (51' RT TO 56' RT)	RT	SINGLE	48", 60", 60"	1	2
			TOTAL	1	2
			SAY	1	2

5/28/99

7/2/2015
2:16:07 PM
S:\roadway\proj\R2603_rdy_psh03B-3_Sum_PvmtRem_SBG_Fence.dgn