PROJECT REFERENCE NO.	SHEET NO.
R-2603	PMP-2

APPROVED: DocuSigned by: Ron King 13E7AF7B9AA4448...

DATE: 5/29/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 022959 ENGINEER RONALD W. KING

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	FINAL PAVEMENT MARKINGS
		THERMO(24", 120 MILS)
T2	WHITE STOPBAR	
T3	WHITE CROSSWALK LINE	
		POLYUREA (4") Highly Reflective Elements
V8	2 FT. - 6 FT./SP WHITE MINISKIP	
VA	WHITE EDGELINE	
VB	YELLOW EDGELINE	
VC	10 FT. WHITE SKIP	
VD	3 FT. - 9 FT./SP WHITE MINISKIP	
VE	WHITE SOLID LANE LINE	
VF	10 FT. YELLOW SKIP	
VH	YELLOW SINGLE CENTER	
VI	YELLOW DOUBLE CENTER	
		POLYUREA (8") Highly Reflective Elements
VN	WHITE GORELINE	
		THERMO(8", 120 MILS)
TQ	WHITE CROSSWALK LINE	
		THERMO(8", 90 MILS)
TO	WHITE DIAGONAL	
TP	YELLOW DIAGONAL	
		THERMOPAVEMENT MARKING SYMBOLS (90 MILS)
UA	LEFT TURN ARROW	
UB	RIGHT TURN ARROW	
UC	STRAIGHT ARROW	
UE	COMBO. RIGHT/STRAIGHT ARROW	
UF	COMBO. LEFT/RIGHT ARROW	
UG	COMBO. LEFT/RIGHT/STRAIGHT ARROW	
UP	MERGE ARROW	
UT	U-TURN ARROW	
		MARKERS
		PERMANENT RAISED PAVEMENT MARKERS
MA	YELLOW & YELLOW	
MB	CRYSTAL & RED	
		SNOWPLOWABLE RAISED PAVEMENT MARKERS
ME	YELLOW & YELLOW	
MF	CRYSTAL & RED	

PAVEMENT MARKING SCHEDULE

28-May-2015 13:18
R:\Projects\R2603\Traffic\Signing\CADD\Quantities & GM Signs\R-2603 PMP Qties.dgn
jamartinez@ST TE27140