



NOTIFY THE DIVISION TRAFFIC ENGINEER (MR. DANIEL ADAMS), AT (336) 903-9136 5 DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEMS COMMUNICATIONS CABLE. NOTIFY THE TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY.

INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING:
REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

- 1) SPLICE LOCATION
- 2) DATE
- 3) COMPANY NAME
- 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

NOTE:

1) TRANSCEIVER TERMINATIONS CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING\ ENSURING PROPER TERMINATIONS.

	SPLICE DETAILS		
	DIVISION 11 WILKES COUNTY NORTH WILKESBORO PLAN DATE: JANUARY 2015 REVIEWED BY: Nick Avery PREPARED BY: P. C. LOUDER REVIEWED BY: 09F50B4CBED3443		