T.I.P.: B-2500AB

ONTRACT:

BASIR A. RASHID

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN DARE COUNTY

LOCATION: PHASE II, NC-12 SHORT-TERM IMPROVEMENTS AT PEA ISLAND

TIP NO.	SHEET NO.	
B-2500AB	SIGN-1	
APPROVED: Ayman Alqudwah F32AC5CAF965472		
DATE: 8/20/2015		
SEAL SEAL 028387 NGINEE NAN I. ALQUITITIES		

SUMMARY OF QUANTITIES

ITEM N	١٥.	TTEM DECODIDITION	QUANTITY	UNIT
DESC. NO.	SECT. NO.	ITEM DESCRIPTION		
4082000000		SUPPORTS, WOOD	84	L.F.
4102000000	904	SIGN ERECTION, TYPE E	6	EA.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO. TITLE

904.10 ORIENTATION OF GROUND MOUNTED SIGNS

904.50 MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL $^\prime\text{E}^\prime$ AND $^\prime\text{F}^\prime$ SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

AYMAN ALQUDWAH, PE, CPM, SIGNING & DELINEATION REGIONAL ENGINEER

SIGNING & DELINEATION PROJECT DESIGN ENGINEER



SHEET NO.

<u>DESCRIPTION</u>

SIGN-1

TITLE SHEET

SIGN-2

SIGN DETAIL SHEET & TYPE "E" SIGNS