Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, removal of existing concrete pavement and clearing and grubbing will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-2500AB	X-1B

CROSS-SECTION SUMMARY

Station -ELN- (NC 12 SOUTH END REPAIR)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3106+40.00	0	0
3107+00.00	0	2
3108+00.00	0	4
3109+00.00	0	4
3110+00.00	15	2
3111+00.00	30	0
3112+00.00	24	0
3113+00.00	13	6
3114+00.00	11	11
3115+00.00	33	6
3116+00.00	39	2
3117+00.00	24	4
3118+00.00	19	4
3119+00.00	19	4
3120+00.00	24	2
3121+00.00	28	0
3122+00.00	28	0
3123+00.00	24	0
3124+00.00	22	0
3125+00.00	24	0
3126+00.00	26	0
3127+00.00	26	0
3128+00.00	13	2
3129+00.00	0	4
3130+00.00	0	4
3131+00.00	0	4
3132+00.00	0	4
3133+00.00	0	2
3134+00.00	0	2
3135+00.00	0	4
3136+00.00	0	4
3137+00.00	4	4
3138+00.00	4	4
3139+00.00	0	4
3140+00.00	0	2
3141+00.00	0	2
3141+50.00	0	2

Station -ELN- (NC 12 SOUTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3076+40.00	0	0
3077+00.00	0	3
3078+00.00	0	11
3079+00.00	6	9
3080+00.00	26	6
3081+00.00	61	2
3082+00.00	91	0
3083+00.00	106	0
3084+00.00	100	0
3085+00.00	89	0
3086+00.00	133	0
3087+00.00	276	0

Station -ELN- (NC 12 SOUTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3088+00.00	380	0
3089+00.00	365	0
3090+00.00	293	0
3091+00.00	202	0
3092+00.00	152	0
3093+00.00	131	0
3094+00.00	120	0
3095+00.00	133	0
3096+00.00	178	0
3097+00.00	254	0
3098+00.00	320	0
3099+00.00	302	0
3100+00.00	233	0
3101+00.00	206	0
3102+00.00	231	0
3103+00.00	241	0
3104+00.00	209	0
3105+00.00	181	0
3106+00.00	161	0
3106+40.00	61	0

Station -ELN- (NC 12 SOUTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3106+40.00	0	0
3107+00.00	89	0
3108+00.00	150	0
3109+00.00	157	0
3110+00.00	169	0
3111+00.00	157	0
3112+00.00	126	0
3113+00.00	100	0
3114+00.00	87	0
3115+00.00	89	0
3116+00.00	119	0
3117+00.00	180	0
3118+00.00	222	0
3119+00.00	200	0
3120+00.00	137	0
3121+00.00	113	0
3122+00.00	139	0
3123+00.00	154	0
3124+00.00	148	0
3125+00.00	141	0
3126+00.00	135	0
3127+00.00	131	0
3128+00.00	128	0
3129+00.00	128	0
3130+00.00	137	0
3131+00.00	141	0
3132+00.00	130	0
3133+00.00	120	0
3134+00.00	115	0

Station -ELN- (NC 12 SOUTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3135+00.00	93	0
3136+00.00	74	0
3137+00.00	80	0
3138+00.00	100	0
3139+00.00	119	0
3140+00.00	119	0
3141+00.00	83	0
3141+50.00	54	1

Station -ELN- (NC 12 NORTH END REPAIR)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3195+18.45	0	1
3195+50.00	0	0
3196+00.00	0	2
3197+00.00	0	2
3198+00.00	0	0
3199+00.00	0	0
3200+00.00	0	2
3201+00.00	0	6
3202+00.00	0	6
3203+00.00	0	4
3204+00.00	2	2
3205+00.00	6	0
3206+00.00	11	0
3207+00.00	9	0
3208+00.00	6	0
3209+00.00	6	0
3210+00.00	4	0
3211+00.00	2	0
3212+00.00	0	2
3213+00.00	0	4
3214+00.00	0	2

Station -ELN- (NC 12 NORTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3195+18.45	0	0
3195+50.00	21	0
3196+00.00	31	0
3197+00.00	59	0
3198+00.00	61	0
3199+00.00	67	0
3200+00.00	69	0
3201+00.00	65	0
3202+00.00	61	0
3203+00.00	61	0
3204+00.00	59	0
3205+00.00	76	0
3206+00.00	115	0
3207+00.00	144	0
3208+00.00	146	0
3209+00.00	109	0

Station -ELN- (NC 12 NORTH END REMOVAL)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
3210+00.00	70	0
3211+00.00	54	2
3212+00.00	50	4
3213+00.00	56	4
3214+00.00	30	2