

North Carolina DOT Division of Highways

Single Trip Permit #212109N0091



Valid From: 12/10/2012 to 12/19/2012

Issued to:

[Empty box for Issued to]

Phone: [Empty box]

State Fee: \$255.00

Sent by: [Empty box]

Load Description: CONCRETE PILING

Escorts: 2

Power Unit: TRUCK-TRACTOR

License: [Empty box]

Registered weight: 80,000

VIN: [Empty box]

Axles: 13

Vehicle 2: SEMI-TRAILER

License: [Empty box]

Dimensions - Length: 165'0"

Width: 8'6"

Height: 14'0"

Trailer:

Overhang - Front: NONE

Rear: 8'0"

VEHICLE(S) MUST BE PROPERLY LICENSED FOR MAXIMUM WEIGHT ALLOWED BY LAW

GrossWeight: 205,500

Table with 13 columns (Axle 1-13) and 3 rows (Weight, Spacing) showing specifications for each axle.

From: SOUTH CAROLINA LINE

To: DARE COUNTY

Permit does not authorize travel on routes beyond "From", point of origin or "To", destination specified.

Via Routes: FROM THE SOUTH CAROLINA LINE ON I-95 NORTH TO EXIT 138 TO US64 EAST TO US64/264 EAST TO US64 EAST TO NC12 TO A POINT ON NC12 AT NCDOT PROJECT #C202185

The route from a specific origin to a specific destination must be included within a single permitted route of travel.

Permits issued by the Department of Transportation do not authorize travel on city streets, such authority must be obtained from the city/municipality prior to movement of permitted load.

Issuance of a permit by the NCDOT does not imply nor guarantee the clearance of width or height along permitted route of travel. It is the responsibility of permit holder to check route prior to travel thereon.

Permittee to follow all detours authorized by DOT or law enforcement. Use extreme safety precautions and obey posted speed limits while traveling into or through all DOT authorized construction workzones.

Permit not valid when: visibility is less than 500 feet; highway covered with ice or snow; or travel conditions are considered unsafe by the Division of Highways or law enforcement having jurisdiction.

The commodity being transported is to be so loaded or reduced to the least possible dimension and/or weight prior to application for an overdimension and/or overweight permit.

Dimensions and/or weights different from those stated on the permit shall not eliminate the escort requirement indicated on this document. Escort vehicle(s) shall be equipped with: flashing amber lights, rotating sealed beam or strobe, minimum 5 inch diameter base and a minimum 4 inch lens height to be mounted on top of escort vehicle, display a banner, yellow in color, mounted on bumper or roof bearing the legend "WIDE LOAD" or "OVERSIZED LOAD" in black (10 inch X 1 1/2 inch) brush stroke lettering visible from front or rear as required by location of escort.

The driver of the escort vehicle is required to be certified in accordance with the North Carolina Escort Vehicle Operator Certification Program.

Power unit and escort vehicle must maintain radio contact and burn headlamps during movement.

Escort vehicle/transporters shall monitor trailing traffic build up and pull to the roadside periodically as the opportunity arises to allow line of traffic to clear.

Escort must be a truck (single vehicle) of not less than 1/4 ton rated load capacity but not more than 17,000 lbs GVWR or a single vehicle passenger vehicle of not less than 2,000 lbs gross weight.

Escort vehicle shall display on both sides of vehicle placards/identification signs measuring 8" by 12" providing escort company's or individual's name and telephone number.

Escort vehicle is not authorized to tow a trailer.

Convoy travel is NOT authorized. Permitted vehicles owned or leased by the same company or permitted vehicles originating at the same location shall travel at a distance of not less than two miles apart.

No driver or passenger other than a certified escort vehicle operator will be allowed to travel in the escort vehicle.

Vehicle must be properly registered or apportioned to operate in North Carolina prior to movement.

Special Restrictions

RED OR ORANGE FLAGS (18" BY 18") TO BE DISPLAYED ON EACH CORNER OF THE LOAD AT THE WIDEST POINT ON LOADS WITH WIDTH EXCEEDING 8FT 6INCHES.

TRAVEL AUTHORIZED MONDAY THROUGH SATURDAY SUNRISE TO SUNSET. SUNRISE AND SUNSET IS DETERMINED BY THE TIME PUBLISHED BY THE UNITED STATES NAVAL OBSERVATORY ACCORDING TO THE VEHICLE'S CURRENT LOCATION.

REAR ESCORT REQUIRED.

MAY TRAVEL POSTED SPEED LIMIT


FRONT ESCORT REQUIRED WHEN GROSS WEIGHT EXCEEDS 149,999 LBS.

DUE TO THE OFFICIAL THANKSGIVING DAY HOLIDAY THERE WILL BE NO TRAVEL FROM NOON WEDNESDAY 11/21/12 UNTIL NOON FRIDAY 11/23/12.

Permittee is responsible for any/all damages to persons/property. Civil penalties will be assessed if: operating off route, transporting improper load, in violation of escort requirements, operating with improper safety equipment or license, failure to comply with dimensions and/or weights of permit, failure to comply with travel restrictions or falsification of a permit application.

PERMIT SHALL BE SIGNED AND CARRIED IN TOWING VEHICLE DURING MOVEMENT.

I CERTIFY THAT I AM FAMILIAR WITH ALL LAWS/ REQUIREMENTS GOVERNING THIS MOVE AND WILL BE IN FULL COMPLIANCE DURING MOVEMENT. ANY ALTERATION(S) WILL RESULT IN VOIDING PERMIT AND SUSPENSION OF NC PERMIT PRIVILEGES. REPEATED PERMIT VIOLATIONS MAY RESULT IN SUSPENSION AND/ OR DENIAL OF NC PERMIT PRIVILEGES.


Director of Permits

Permittee Signature

Date

2184399

CS5

Authorized: 12/10/12 9:56 am