(FINAL PAVEMENT DESIGN JANUARY 31,2014) (REVISED MAY 22,2014)			
C1	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.IN EACH OF TWO LAYERS.	E5	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.	J	PROP. 10" AGGREGATE BASE COURSE
С3	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.	Р	PRIME COAT AT A RATE OF 0.35 GAL. PER SQ. YD.
C4	PROP. APPROX. 2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 224 LBS. PER SQ. YD.	R1	2'-6" CONCRETE CURB AND GUTTER
C5	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.	R2	5" MONOLITHIC CONCRETE ISLAND (KEYED-IN)
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	S	4" STAMPED CONCRETE SIDEWALK
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 2½" OR GREATER THAN 4" IN DEPTH.	Т	EARTH MATERIAL
D3	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD.	U	EXISTING PAVEMENT

V2

PROP. APPROX. 4.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD.

PROP. APPROX. 7" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B,


PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT GREATER THAN  $5\frac{1}{2}$ " IN DEPTH OR LESS

THAN 4" IN DEPTH.


AT AN AVERAGE RATE OF 399 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.

PROP. APPROX. 10.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 598.5 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.

PROJECT REFERENCE NO. SHEET NO. B-3159 2A-/ R/W SHEET NO. ROADWAY DESIGN 022896 Clark S Morrison



Detail Showing Method of Wedging



3" MILLING

VARIABLE DEPTH MILLING - 0" TO 3"

VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL).

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

USE TYPICAL SECTION NO. 1 -L- STA. 7+75.00 TO 8+00.00

NOTES: FLOAT CROWN POINT AND WARP SUPERELEVATIONS TO TIE TO EXISTING AT 7+75.00. MILL AS NEEDED.