| PROJ. REFERENCE NO. | SHEET NO. |
|---|---|
| B-4959 | X-1A |

# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS

## *CROSS-SECTION SUMMARY*

**Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal ofexisting asphalt pavement will be paid for at the lump sum price for "Grading".**

**NOTE: EMBANKMENT COLUMN DOES NOT INCLUDES BACKFILL FOR UNDERCUT**

| Station<br>L | Uncl. Exc.<br>(cu. yd.) | Embt<br>(cu. yd.) |
|---|---|---|
| 12+00.00 | 0 | 0 |
| 12+50.00 | 7 | 6 |
| 12+85.75 | 11 | 5 |
| 13+00.00 | 89 | 1 |
| 13+50.00 | 333 | 3 |
| 13+99.21 | 67 | 2 |

| Station<br>L | Uncl. Exc.<br>(cu. yd.) | Embt<br>(cu. yd.) |
|---|---|---|
| 15+41.80 | 0 | 0 |
| 15+50.00 | 1 | 13 |
| 16+00.00 | 17 | 68 |
| 16+50.00 | 34 | 34 |
| 17+00.00 | 42 | 14 |
| 17+50.00 | 41 | 12 |
| 18+00.00 | 44 | 10 |
| 18+50.00 | 27 | 11 |
| 18+70.00 | 2 | 4 |

| Station<br>Y | Uncl. Exc.<br>(cu. yd.) | Embt<br>(cu. yd.) |
|---|---|---|
| 10+50.00 | 0 | 0 |
| 11+00.00 | 6 | 3 |
| 11+50.00 | 3 | 11 |
| 12+00.00 | 28 | 9 |
| 12+50.00 | 87 | 8 |