

EMERGENCY VEHICLE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)


From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #2.

PREEMPTION #2	SETTINGS (NEXT:1-10)
INTERVAL/TIMING	CLEAR/DWELL PHASES
GRN YEL RED	12345678910111213141516
1 255 0.0 0.0	X X
2 0 0.0 0.0	
3 0 0.0 0.0	
4 0 0.0 0.0	
5 1 0.0 0.0	X X
EXIT CALLS	
OPTIONS	
PRIORITY (Y/N TO SELECT)MED
DELAY TIMER (0-255 SEC)*
MIN GREEN BEFORE PRE (0= DEFAULT)	...1
PED CLEAR BEFORE PRE (0= DEFAULT)	...0
YELLOW CLEAR BEFORE PRE (0= DEFAULT)	...0.0
RED CLEAR BEFORE PRE (0= DEFAULT)	...0.0
DWELL MIN TIMER (0-255 SEC)*
DWELL MAX TIMER (0=OFF,1-255MIN)	...2
DWELL HOLD-OVER TIMER (0-255)0
LATCH CALL?Y
LINK TO NEXT PREEMPT?N
ENABLE BACKUP PROTECTION?N
HOLD CLEAR 1 PHASES DURING DELAY?	...N
FAST GREEN FLASH DWELL PHASES?N
PED CLEARANCE THROUGH YELLOW?N
INHIBIT OVERLAP GREEN EXTENSION?N
SERVICE DURING SOFTWARE FLASH?N
REST IN RED DURING DWELL INTERVAL?	..N
FLASH DWELL INTERVAL?N
ALLOW PEDS IN DWELL INTERVAL?N
RE-TIME DWELL INTERVAL?Y
OVERLAPS:	ABCDEFGHIJKLMNOP
DWELL INT FLASH YELLOW	
OMIT OVERLAPS:	

* Denotes timing to be determined in field.

EV Preemption Control Box Wiring Detail

(wire as shown below)



PHASE 2 PED YELLOW (114)

AC NEUTRAL (T1-2)


LAMP NOTES

1. If field terminal 114 has a conflict monitor wire attached, remove, tape, and label wire.
2. Make sure load resistors are in place as shown in the Load Resistor Installation Detail on sheet 1.
3. Install a loadswitch in Output File Slot S3.

NOTES


1. Relay K1 is shown in the energized (Preempt not active) normal operation state.
2. Relay K1 is a DPDT with 120VAC coil with an octal base.
3. Relay SSR1 is a SPST (normally open) Solid State Relay with AC input and AC (25 amp) output.
4. AC Isolator Card shall activate preemption upon removal of AC+ from the input (as shown above). To accomplish this, set invert dip switch on AC Isolator Card.
5. IMPORTANT!! Terminal TB9-12 (on input panel) shall be connected to AC neutral (jumper may have to be added).

FRONT VIEW



PREEMPT 2 AC ISOLATOR (MODEL 252) OUTPUT PROGRAMMING DETAIL

(set DIP switches as shown below)



NOTE: IF ANOTHER MANUFACTURER TYPE OF AC ISOLATOR IS USED, OUTPUT PROGRAMMING IS LIKELY NOT TO EQUATE TO THAT SHOWN ABOVE.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 07-0493
 DESIGNED: November 2014
 SEALED: 3/4/2015
 REVISED: N/A

Electrical Detail - Sheet 3 of 3

	NC 68 (Eastchester Drive) at SR 1541 (W. Wendover Avenue) and SR 1820 (Skeet Club Road)	SEAL
Prepared in the Offices of: S. ARMSTRONG Electrical and Programming 750 N. Greenfield Pkwy, Garner, NC 27529	PLAN DATE: December 2014 PREPARED BY: S. Armstrong REVIEWED BY: JTR	Division 7 Guilford County High Point, NC DATE: 3/5/2015 SIG. INVENTORY NO. 07-0493

05-1485-2014-08-02
 S:\MITS\15\SIGNAL\work\hgr\output\sig\Map\hgr\str\ong\070493_sml.ele.xxx.dgn
 sarmstrong