


### EDI MODEL 2018ECLip-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



### NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all phases.
- Program phases 2 and 6 for Start Up In Green.
- Program phases 2 and 6 for Yellow Flash.
- The cabinet and controller are part of the High Point Signal System.

### SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	NU	21,22	NU	NU	41,42 43	NU	NU	61,62	NU	NU	81,82 83	NU
RED		128			101			134			107	
YELLOW		129			102			135			108	
GREEN		130			103			136			109	
RED ARROW												
YELLOW ARROW												
GREEN ARROW												


NU = Not Used

### EQUIPMENT INFORMATION

CONTROLLER.....2070  
 CABINET.....332  
 SOFTWARE.....ECONOLITE OASIS  
 CABINET MOUNT.....BASE  
 OUTPUT FILE POSITIONS...12  
 LOAD SWITCHES USED.....S2,S5,S8,S11  
 PHASES USED.....2,4,6,8  
 OVERLAPS.....NONE

### INPUT FILE POSITION LAYOUT


(front view)



### INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
4A	TB4-9,10	I6U	41	3	4	4	Y	Y			3
8A	TB5-9,10	J6U	42	4	8	8	Y	Y			3
* S1	TB6-9,10	I9U	60	22	11	SYS					
* S2	TB6-11,12	I9L	62	24	13	SYS					

\* System detector only. Remove the vehicle phase assigned to this detector in the default programming.



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 07-1005  
 DESIGNED: September 2014  
 SEALED: 3/11/15  
 REVISED: N/A

### Electrical Detail

Electrical and Programming Details for: SR 1009 (South Main Street) at Coltrane Avenue and South Centennial Street

Division 7 Guilford County High Point

PLAN DATE: November 2014 REVIEWED BY: T. Joyce

PREPARED BY: B. SIMMONS REVIEWED BY:

REVISIONS INIT. DATE

Seal: GEORGE C. BROWN, PROFESSIONAL ENGINEER, SEAL 022013

DocuSigned by: George C. Brown 3/17/2015

750 N. Greenfield Pkwy, Garner, NC 27529

SIG. INVENTORY NO. 07-1005

I:\MSB-2014-06-55  
 S:\MITSU\15 Signal\working\pous\g\Map\5\mms\working\Folder\High Point\071005-smc.ele\_xxx.dgn  
 bis\simmons