SUMMARY OF WORK BY CABLE ROUTING PLANS

CABLE ROUTING SHEET NUMBER	COMMUNICATIONS CABLE (24-FIBER)	COMMUNICATIONS CABLE (36-FIBER)	DROP CABLE (6-FIBER)	HANDLASH & AERIAL CABLE PROTECTOR	SPLICE ENCLOSURE	MODIFY EXISTING SPLICE	INTERCONNECT CENTER			REMOVE SPLICE CABINET	REMOVE CCTV CABINET	INSTALL CCTV CAMERA ASSEMBLY	REMOVE EX CCTV ASSEMBLY	INSTALL CCTV CABINET (336A POLE)	, INSTALL CCT CABINET ' (NEMA 4, POLE)	V INSTALL CCTV CABINET (336A BUILDING)	INSTALL CCTV CABINET (336A, BASE) WTH FOUNDATION		ETHERNET CABLE (CAT) 5E)	LOW VOLTAGE POWER CABLE (24VAC)		INSTALL DISCONNECT FOR CCTV	NEW ELEC SERVICE FOR CCTV	INSTALL 5/8" x 10' GROUNDING ELECTRODE FOR POWER	ENCODER
	LF	LF	LF	LF	EA	EA	EA	EA	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA EA	LF	LF	EA	EA	EA	EA	EA
CRP-6.001	1,540	-	70	-	1	-	1	1	415	-	1	1	1	-	1	-	-		90	90	-	-	-	-	-
CRP-6.002	1,530	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.003	1,575	-	100	-	1	-	1	1	535	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.004	1,500	-	-	-	-	-	-	-	-	-	-	-	-	-	-	•	-		-	-	-	-	-	-	-
CRP-6.005	1,610	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.006	2,165	-	490	-	2	-	1	1	630	1	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.007	1,240	-	415	-	-	-	1	1	40	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.008	1,320	-	295	-	1	-	1	1	-	-	-	1	-	-	1	-	-	1 -	180	180	-	-	-	-	-
CRP-6.009	1,470	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.010	1,530	-	250	-	1	-	1	1	220	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.011	1,620	-	80	-	1	-	1	1	765	-	-	-	•	-	-	•	-		-	-	-	-	-	-	-
CRP-6.012	2,465	-	425	-	1	-	2	2	285	-	1	1	1	1	-	-	-		-	-	-	-	1	3	-
CRP-6.013	1,630	-	100	-	1	-	1	1	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.014	545	-	315	-	1	-	1	1	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.015	1,160	-	-	-	-	-	-	-	120	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.016	1,520	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.017	1,660	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.018	270	-	325	-	1	-	1	1	120	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.019	125	-	170	-	1	-	1	1	570	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.020	1,560	-	-	-	-	-	-	-	530	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.021	1,605	-	310	-	1	-	1	1	325	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.022	1,465	-	285	-	1	-	1	1	345	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.023	2,105	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.024	1,365	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.025	1,585	-	-	-	-	-	-	-	535	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.026	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.027	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.028	1,055	-	70	-	1	-	1	1	445	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.029	1,530	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.030	1,610	-	225	-	1	-	1	1	210	-	-	1	-	-	1	-	-	1 -	45	45	-	-	-	-	-
CRP-6.031	855	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.032	1,340	-	-	-	-	•	-	-	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.033	1,595	-	200	-	1	-	1	1	-	-	-	-	-	-	-	-	-		-	-	-	-	-	-	-
CRP-6.034	1,965	-	350	-	2	-	2	2	390	-	-	1	-	-	1	-	-	- 1	240	240	-	-	-	-	-
CRP-6.035	1,940	-	75	-	2	•	1	1	-	1	-	-	-	-	-	-	-		-	-	-	-	-		-

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III. - The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantites and the Project Special Provisions for defined Pay Items for this contract.



ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310 RALEIGH, NORTH CAROLINA 27609 (919) 876-6888 NCBEES #F-0326

PROJECT REFERENCE NO. SHEET C-5558

E NO.	CRP-1	
		.00

Prepare	ed for the Offices of:	High	Point	SEAL						
In I I I I I I I I I I I I I I I I I I	NORTH CREATER SWA		ımmary ble Roı (sheet	SEAL						
ellie	A AND AND AND AND AND AND AND AND AND AN	Division 7	Guilf	ord County	High	Point				
n _t	Transportation	PLAN DATE: J	une 2015	REVIEWED BY:	MB Tot	h	THE ENGINEER A			
750 Greenfield	Parkway, Garner, NC 27529	PREPARED BY:	LMM	REVIEWED BY:	LM Moon		S S S S S S S S S S S S S S S S S S S			
	SCALE	REVI	SIONS		INIT.	DATE	DocuSigned by:			
	NTS						Melissa B. Toth 6/5/2015 D86DCF8E04D04AF DATE			
							CADD Filename: CRP-1.001.dgn			