



08-JUN-2015 09:19 T:\projects\104115\ANDOT\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail1-06.dgn SLOC3653 AT LUS291201

COLOR CODE		LEGEND	
TABLE	598-B		
(1) BLUE	(7) RED	X = FUSION SPlice INDIVIDUAL FIBER	
(2) ORANGE	(8) BLACK	C = CAP AND SEAL	
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING	
(4) BROWN	(10) VIOLET	BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR	
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

NOTES
1. UNUSED FIBERS LEFT COILED AND STORED IN SPICE TRAY
2. UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPICE ENCLOSURE
3. EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
(919) 876-6888 NCBEES #F-0326

<p>Prepared for the Offices of: Transportation Mobility and Safety Division STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION 750 Greenfield Parkway, Garner, NC 27529</p>	High Point Signal System Splicing Details		SEAL 019962 HENRY W. BADGETT ENGINEER 6/8/2015
	Division 7 Guilford County High Point PLAN DATE: June 2015 REVIEWED BY: HA Badgett PREPARED BY: BJ Slocum REVIEWED BY: SG Haynie	REVISIONS INIT. DATE	
SCALE: NTS			CADD Filename: SpliceDetail1-06.dgn