



08-JUN-2015 09:19 T:\projects\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail1-07.dgn S:\033653 AT LUS291201

#### LEGEND

COLOR CODE TIA/EIA 598-B	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

  

X	= FUSION SPlice INDIVIDUAL FIBER
C	= CAP AND SEAL
EXPRESS	= EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
BUFFER SPlice	= SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR

- #### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
  - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
  - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

## ATKINS

1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEES #F-0326

SEAL

DocuSigned by:  
**HA Badgett**  
6/8/2015

### High Point Signal System Splicing Details

Division 7		Guilford County		High Point	
PLAN DATE:	June 2015	REVIEWED BY:	HA Badgett		
PREPARED BY:	BJ Slocum	REVIEWED BY:	SG Haynie		
SCALE		REVISIONS		INIT.	DATE
NTS					

CADD Filename: SpliceDetail1-07.dgn