



08- JUN-2015 09:20 T:\projects\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail1-55.dgn SLOC3653 AT LUS291201

COLOR CODE	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

  

LEGEND	
X	= FUSION SPlice INDIVIDUAL FIBER
C	= CAP AND SEAL
EXPRESS	= EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
BUFFER SPlice	= SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR

- ### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
  - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
  - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

## ATKINS

1616 EAST MILLBROOK ROAD, SUITE 310  
 RALEIGH, NORTH CAROLINA 27609  
 (919) 876-6888 NCBEES #F-0326

SEAL

<b>High Point Signal System Splicing Details</b>	
Division 7	Guilford County High Point
PLAN DATE: June 2015	REVIEWED BY: HA Badgett
PREPARED BY: BJ Slocum	REVIEWED BY: SG Haynie
SCALE: NTS	DATE: 6/8/2015

DocuSigned by: *HA Badgett* 6/8/2015  
 CADD Filename: SpliceDetail1-55.dgn