



SPlice ENCLOSURE NO. S13-7							
DEVICE ID	CL SHEET	CABLE X			CABLE Y		
		CABLE NUMBER	ALONG ROUTE	TO	CABLE NUMBER	ALONG ROUTE	TO
08-0707	CRP-6.044	13E	SURRETT DR	W FAIRFIELD RD	13E	SURRETT DR	SEALY DR
07-0809	CRP-6.035	13C	W GREEN DR	AMHURST AVE	13C	W GREEN DR	I-85 BUSINESS SB RAMPS
07-0416	CRP-6.034	13C	W GREEN DR	TRINITY AVE	13C	W FAIRFIELD RD	I-85 BUSINESS NB RAMPS
07-0200	CRP-6.033	13C	W FAIRFIELD RD	I-85 BUSINESS NB RAMPS	13C	W FAIRFIELD RD	SURRETT DR

COLOR CODE TIA/EIA 598-B		LEGEND	
(1) BLUE	(7) RED	X = FUSION SPlice INDIVIDUAL FIBER	
(2) ORANGE	(8) BLACK	C = CAP AND SEAL	
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING	
(4) BROWN	(10) VIOLET	BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR	
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

- ### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
  - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
  - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

**ATKINS** 1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEES #F-0326

08-UN-2015-09-20  
T:\project\108115\ANDOT\100037777 - High Point Sig Sys\Comms and ITS\Fiber Splicing\SpliceDetail1-57.dgn  
SLOCUM AT LUS291201

<p>Prepared for the Offices of:</p> <p>750 Greenfield Parkway, Garner, NC 27529</p>	<p>High Point Signal System Splicing Details</p>		<p>SEAL</p>
	<p>Division 7      Guilford County      High Point</p>	<p>PLAN DATE: June 2015      REVIEWED BY: HA Badgett</p>	
	<p>PREPARED BY: BJ Slocum      REVIEWED BY: SG Haynie</p>	<p>REVISIONS: _____ INIT. DATE</p>	
SCALE: NTS			<p>DocuSigned by: <b>HA Badgett</b> 6/8/2015 DATE</p>

CADD Filename: SpliceDetail1-57.dgn