



08-JUN-2015 09:21 T:\projects\highpoint\splicing\splicingdetails\172.dgn S:\C03653 AT LUS291201

COLOR CODE TABLE 598-B	
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

LEGEND	
X	FUSION SPlice INDIVIDUAL FIBER
C	CAP AND SEAL
EXPRESS	EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
BUFFER SPlice	SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR

- ### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
 - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
 - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

ATKINS

1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
(919) 876-6888 NCBEES #F-0326

SEAL

High Point Signal System Splicing Details

Division 7	Guilford County	High Point
PLAN DATE: June 2015	REVIEWED BY: HA Badgett	
PREPARED BY: BJ Slocum	REVIEWED BY: SG Haynie	

REVISIONS	INIT.	DATE

DocuSigned by: **Ally Badgett** 6/8/2015

DATE

CADD Filename: SpliceDetail-172.dgn