Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
U-5104	X-1A

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+28.80	0	0	26+04.00	0	3	45+00.00	20	0	10+91.62	0	0
10+50.00	13	2	26+50.00	7	40	45+43.75	8	0	11+00.00	1	0
10+75.00	22	17	26+85.00	11	33				11+25.00	8	3
11+00.00	13	26	27+00.00	3	17	**Station Y2**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
11+28.00	9	24	27+16.00	0	23				**Station Y5**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
11+50.00	6	22	27+50.00	1	47						
12+00.00	13	67	28+00.00	1	51	10+90.00	0	0	SKIP STATION RANGE = 11+50.00 to 11+75.00		
12+34.00	7	45	28+50.00	2	40	11+00.00	4	0	11+00.00	0	0
12+50.00	3	15	28+90.00	3	26	11+25.00	21	3	12+25.00	8	2
13+00.00	17	30	29+00.00	1	8	11+50.00	17	6	12+30.85	1	0
13+25.00	9	12	29+10.00	1	9	11+75.00	12	5			
13+35.00	3	3	29+50.00	3	29	12+00.00	9	3	**Station Y6**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
13+50.00	5	3	29+93.00	2	33						
13+59.00	3	1	30+00.00	0	5	**Station Y3**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**	11+00.00	0	0
14+00.00	45	3	30+50.00	2	38				11+50.00	0	0
14+50.00	94	3	30+70.00	1	15	7+70.00	0	0	12+00.00	0	0
15+00.00	81	6	30+90.00	1	14	7+75.00	0	0	12+08.50	1	0
15+47.00	52	2	31+00.00	1	7	8+00.00	4	0	12+28.00	0	0
15+50.00	3	0	31+30.00	9	14	8+25.00	4	0			
16+00.00	46	4	31+42.00	5	3	8+50.00	4	0	**Station Dr1**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**
16+18.00	17	2	31+50.00	4	1	8+75.00	4	0			
16+38.00	20	1	32+00.00	32	7	9+00.00	4	0	10+10.70	0	0
16+50.00	11	0	32+50.00	37	8	9+25.00	3	0	10+25.00	4	0
17+00.00	41	2	32+65.00	10	2	9+50.00	3	0	10+50.00	28	0
17+20.00	16	1	33+00.00	22	4	9+75.00	3	0	10+75.00	52	0
17+50.00	34	1	33+50.00	28	8	10+00.00	3	0	10+98.27	29	0
17+78.00	31	1	33+88.00	23	6	10+25.00	3	0			
18+00.00	18	1	34+00.00	7	2	10+50.00	3	0			
18+29.00	18	1	34+42.00	21	8	10+75.00	1	0			
18+50.00	13	3	34+50.00	4	2						
19+00.00	33	23	35+00.00	28	11	**Station Y3**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
19+19.00	9	10	35+50.00	27	10						
19+50.00	14	8	36+50.00	75	19						
19+78.00	7	1	37+00.00	45	9	SKIP STATION RANGE = 11+00.00 to 11+25.00					
20+00.00	4	13	37+36.00	27	5	11+50.00	0	0			
20+29.00	4	48	37+50.00	10	1	11+75.00	3	16			
20+50.00	1	50	37+84.00	19	6	11+96.82	3	2			
21+00.00	1	110	38+00.00	7	4						
21+50.00	2	90	38+50.00	17	14	**Station Y4**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
22+00.00	8	63	38+61.00	3	3						
22+11.00	3	8	39+00.00	24	5						
22+48.00	37	24	39+50.00	34	2	11+31.00	0	0			
22+50.00	3	1	40+00.00	20	4	11+50.00	2	1			
23+00.00	102	15	40+50.00	24	4						
23+50.00	139	15	41+00.00	26	2	**Station Y4**	**Uncl. Exc. (cu. yd.)**	**Embt (cu. yd.)**			
23+60.00	32	7	41+50.00	25	0						
24+00.00	101	30	42+00.00	23	1						
24+42.00	61	33	43+00.00	40	2	SKIP STATION RANGE = 11+75.00 to 11+75.00					
24+50.00	8	7	43+35.00	15	0	12+00.00	0	0			
25+00.00	44	36	43+50.00	6	0	12+25.00	2	1			
25+05.00	4	2	43+73.00	10	1	12+28.09	0	0			
25+50.00	25	17	44+00.00	12	1						
26+00.00	13	29	44+50.00	20	1						