DocuSign Envelope ID: 7CBF2064-4BCB-405B-B02F-E9440F08996A

PROJECT REFERENCE NO.	SHEET NO.
U-3338B	UC-17

SCALE: 10 0 20

NAD 83/95

NORTH CAROLINA PROFESSIONAL SEAL 7952 ENGINEER DAVID POE

DocuSigned by: DAVID POE EA0976DF4A0F4E8...

6/8/2015

UTILITY CONSTRUCTION

MATCHLINE –L– STA.81+00 SEE SHEET 16

MATCHLINE –L– STA.86+50 SEE SHEET 18

MATCHLINE –Y12– STA.12+50 SEE SHEET 40

PROP. 1 - RELOCATE WATER METER

PROP. 2 - RELOCATE WATER METERS

PROP. - 2 SANITARY SEWER CLEAN-OUT

PROP. RELOCATE FIRE HYDRANT

PROP. 1 - RELOCATE WATER METER

PROP. 1 - RELOCATE WATER METER

REMOVE ALL CONSTRUCTION DEBRIS AND BACKFILL MEDIAN WITH TOPSOIL

BEGIN CONSTRUCTION TIE TO EXIST. C&G -Y11- POT Sta. 12+60.78

-Y11- PTX Sta. 12+75.95

-L- POT Sta. 84+62.55

-Y12- POT Sta. 10+00.00

BRG AH = S 84° 56' 47.8" E

-Y12- PC Sta. 10+41.59

-Y11- PI Sta 12+36.25 D = 23° 03' 45.9" (RT) D = 28° 38' 52.4" L = 80.50' T = 40.80' R = 200.00' SE = 02

-Y12- PI Sta 11+28.96 D = 7° 08' 32.0" (RT) D = 4° 05' 33.2" L = 174.52' T = 87.37' R = 1,400.00' SE = 02

-Y12- PT Sta. 12+16.10

END CONSTRUCTION -Y12- POT Sta. 11+35.76

BEGIN FULL C/A BEGIN CHAIN LINK FENCE -Y11- +60.78 EXIST. R/W

BEGIN FULL C/A BEGIN CHAIN LINK FENCE -Y12- +35.76 EXIST. R/W

TIE TO EXIST. C&G

TIE TO EXIST. C&G

NO CLAIM

86 THOMAS A. BLOUNT, ET UX DB 5057 PG 534 DB 4437 PG 228 MB 44 PG 188 MB 2 PG 132

87 TANYA BELL MILLHOUSE DB 5291PG 2710 DB 4519 PG 822 MB 44 PG 188 MB 2 PG 132

88 MARGARET M. CLARK, ET AL DB 4599 PG 847 MB 44 PG 188 MB 2 PG 132

89 OLGA SELLARS DB 5503 PG 1149 DB 4577 PG 943 MB 44 PG 188 MB 2 PG 132

90 AWW PROPERTIES LLC. DB 5267PG 29 DB 4655 PG 615 MB 43 PG 178 MB 2 PG 132

92 WILMON K. ANDREWS, ET UX DB 4652 PG 821 MB 46 PG 165 MB 2 PG 132

81 CHARLES E. RATCLIFFE, ET UX DB 1442 PG 186 DB 501 PG 138 MB 6 PG 6

85 JUDY P. FORSYTHE DB 2479 PG 022 MB 4 PG 80

94 EVELYN PRYDE DAVIS DB 991PG 1508 DB 1297 PG 957 MB 2 PG 132

95 VANCE W. WRENN DB 5358 PG 1727 DB 5358 PG 1724 DB 4523 PG 081 MB 2 PG 132

97 JASON M. LEWIS DB 4897 PG 646 MB 47 PG 363 MB 47 PG 364 MB 47 PG 365

98 RICHARD B. MITCHELL, ET UX DB 4893 PG 2051 MB 47 PG 364 MB 47 PG 363 MB 47 PG 365

99 DOFLT 93 CASEY TRUST DB 5498 PG 2003 DB 4863 PG 2675 MB 47 PG 363 MB 47 PG 364 MB 47 PG 365

96 SMITH CREEK VILLAGE TOWNHOME ASSOC., INC. DB 4777 PG 681 DB 4760 PG 805 MB 47 PG 324 MB 47 PG 325 MB 47 PG 326 MB 47 PG 327 MB 47 PG 363 MB 47 PG 364 MB 47 PG 365 MB 2 PG 132

101 JAMES M. HARRELL, ET UX DB 1595 PG 334 DB 1828 PG 257 MB 26 PG 34 MB 2 PG 132

Prepared by:

AECOM

AECOM TECHNICAL SERVICES OF NORTH CAROLINA, INC.
701 CORPORATE CENTER DRIVE, SUITE 475, RALEIGH, NC 27607
919-854-6200 919-854-6259 (fax)

DATE: 6/6/2015
DGN: u3338b_uc_psh_slf.dgn