

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.14.02.10871.1	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	3" MILLING SY	1½" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF	ADJ. OF DROP INLET EA	
2016CPT.14.02.10871.1	Swain	1	US 19/74 WEST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	NO	NO	2.57	28	27,138	4,156	100	5,105	4,208	497	27,139		
TOTAL FOR MAP NO. 1										2.57		27,138	4,156	100	5,105	4,208	497	27,139		
2016CPT.14.02.10871.1	Swain	2	US 19/74 EAST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	NO	NO	2.57	28	27,138	3,620	100	5,105	4,156	494	27,139		
TOTAL FOR MAP NO. 2										2.57		27,138	3,620	100	5,105	4,156	494	27,139		
2016CPT.14.02.10871.1	Swain	3	US 19/74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	NO	NO	0.6	75	10,138	850	500	1,906	2,774	166		11	
TOTAL FOR MAP NO. 3										0.6		10,138	850	500	1,906	2,774	166		11	
2016CPT.14.02.10871.1	Swain	4	RAMP (EXIT 64)	FROM US 19/74 EAST TO US 19	3	1		NO	NO	0.37	24		5,210			484	29			
TOTAL FOR MAP NO. 4										0.37			5,210			484	29			
2016CPT.14.02.10871.1	Swain	5	ACCESS RAMP WEST	FROM US 19 TO US 19/74 WEST	4	1		NO	NO	0.43	24		6,054			552	33			
TOTAL FOR MAP NO. 5										0.43			6,054			552	33			
2016CPT.14.02.10871.1	Swain	6	ACCESS RAMP EAST	FROM US 19 TO US 74 EAST	4	1		NO	NO	0.27	24		3,802			347	21			
TOTAL FOR MAP NO. 6										0.27			3,802			347	21			
TOTAL FOR PROJ NO. 2016CPT.14.02.10871.1										6.81			64,414	23,692	700	12,116	12,521	1,240	54,278	11
GRAND TOTAL										6.81			64,414	23,692	700	12,116	12,521	1,240	54,278	11

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E	4457000000-N	4697000000-E	4710000000-E	4721000000-E	4725000000-E	4810000000-E	4891000000-E	4905000000-N			
										WORK ZONE ADVANCE/GENERAL WARING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	8" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	4" WHITE PAINT LF	4" X 50 M YELLOW THERMO LF	4" X 50 M WHITE THERMO LF	SNOW PLOWABLE MARKERS EA	
2016CPT.14.02.10871.1	Swain	1	US 19/74 WEST	FROM PVT CHG UNDER SR-1140 TO END DIV HWY	1	2	MD	2.57	28	292.0	1	1,028	250	6	13	6	6,785	14,084	20,568	245	
TOTAL FOR MAP NO. 1										292.0	1	1,028	250	6	13	6	6,785	14,084	20,568	245	
2016CPT.14.02.10871.1	Swain	2	US 1974 EAST	FROM BEG DIV HWY TO PVT CHG UNDER SR-1140	1	2	MD	2.57	28	292.0		1,028	250	6	15	2	6,785	14,084	20,568	245	
TOTAL FOR MAP NO. 2										292.0		1,028	250	6	15	2	6,785	14,084	20,568	245	
2016CPT.14.02.10871.1	Swain	3	US 19/74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	0.6	75	67.0			80		2		3,168	7,920	8,160	94	
TOTAL FOR MAP NO. 3										67.0			80		2		3,168	7,920	8,160	94	
2016CPT.14.02.10871.1	Swain	4	EXIT 64 RAMP	FROM US 19/74 EAST TO US 19	3	1		0.37	24									1,953	1,953		
TOTAL FOR MAP NO. 4										0.37									1,953	1,953	
2016CPT.14.02.10871.1	Swain	5	ACCESS RAMP WEST	FROM US 19 TO US 19/74 WEST	4	1		0.43	24	24.0								2,270	2,270	40	
TOTAL FOR MAP NO. 5										24.0									2,270	2,270	40
2016CPT.14.02.10871.1	Swain	6	ACCESS RAMP EAST	FROM US 19 TO US 74 EAST	4	1		0.27	24	24.0								1,425	1,425	40	
TOTAL FOR MAP NO. 6										24									1,425	1,425	40
TOTAL FOR PROJ NO. 2016CPT.14.02.10871.1										699	1	2,056	580	12	38	8	16,738	41,736	54,944	664	
GRAND TOTAL										699	1	2,056	580	12	38	8	16,738	41,736	54,944	664	