

## REFORESTATION

AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION MIXTURE, TYPE, SIZE, AND FURNISH SHALL **35% PLATANUS OCCIDENTALIS 35% LIRIODENDRON TULIPIFERA 30% BETULA NIGRA** 

PROJECT REFERENCE NO.		SHEET NO.
B-5342		RF-I
R/W SHEET NO	0.	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER

TREE REFORESTATION SHALL BE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING,

CONFORM TO THE FOLLOWING:		
AMERICAN SYCAMORE	12 in – 18 in BR	
YELLOW POPLAR	12 in – 18 in BR	
<b>RIVER BIRCH</b>	12 in – 18 in BR	

## **REFORESTATION DETAIL SHEET**

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT