

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

### CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Undercut
L	(cu. yd.)	(cu. yd.)	(cu. yd.)
12+00.0000	0	0	0
12+50.0000	72	11	0
13+00.0000	216	21	0
13+50.0000	276	25	0
14+00.0000	164	28	0
14+50.0000	47	37	0
15+00.0000	30	67	0
15+50.0000	22	96	0
16+00.0000	33	163	0
16+50.0000	65	230	0
16+83.5339	37	167	0
17+00.0000	0	0	0
17+50.0000	0	0	0
17+56.1320	0	0	0
18+00.0000	17	380	59
18+50.0000	14	537	111
19+00.0000	14	516	155
19+50.0000	19	331	100
20+00.0000	173	79	0
20+50.0000	304	4	0
21+00.0000	188	7	0
21+50.0000	48	15	0
22+00.0000	3	25	0
22+50.0000	1	20	0
22+80.0000	1	3	0

Station	Uncl. Exc.	Embt
Dr1	(cu. yd.)	(cu. yd.)
10+00.0000	0	0
10+50.0000	13	6
11+00.0000	0	15
11+50.0000	0	56

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

### CROSS SECTION INDEX SHEET

Chain	Beg Sta	End Sta	Sheet No.
L	12+00.0000	22+80.0000	X-1 TO X-9
Dr1	10+00.0000	11+50.0000	X-10