

PROJECT NO.	SHEET NO.	TOTAL NO.
I-5723	3	

**SUMMARY OF QUANTITIES**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	2.25" MILLING SY	1.5" MILLING SY	SURFACE COURSE, S9.5C TONS	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OGAFC, TYPE FC-1 MOD TON	OGAFC, TYPE FC-2 MOD TON	MILLED RUMBLE STRIPS LF	DROP INLET REPAIR EA	
I-5723	Johnston	1	I-40 EBL	EAST OF I-95 TO SAMPSON CO. LINE	1	2	MD	YES	NO	11	32	217,400			17,414		1,561		9,311	116,000	16	
		2	I-40 WBL	SAMPSON CO. LINE TO EAST OF I-95	1	2	MD	YES	NO	11	32	217,400			17,414		1,561		9,311	116,000	16	
		3	EBL ENTRY RAMP	NC 96 HWY TO EBL I-40	2	2		NO	NO	0.21	22	1,800	2,710	379		22	12	200				
		4	EBL EXIT RAMP	I-40 TO NC 96 HWY	2	2		NO	NO	0.2	22	800	2,581	285		17	9	140				
		5	WBL ENTRY RAMP	NC HWY 96 TO I-40	2	2		NO	NO	0.21	22	1,800	2,710	379		22	9	140				
		6	WBL EXIT RAMP	I-40 TO NC HWY 96	2	2		NO	NO	0.21	22	800	2,710	296		17	12	200				
<b>TOTAL FOR PROJ NO. I-5723</b>										<b>22.83</b>		<b>440,000</b>	<b>10,711</b>	<b>1,339</b>	<b>34,828</b>	<b>78</b>	<b>3,164</b>	<b>680</b>	<b>18,622</b>	<b>232,000</b>	<b>32</b>	
<b>GRAND TOTAL</b>										<b>22.83</b>		<b>440,000</b>	<b>10,711</b>	<b>1,339</b>	<b>34,828</b>	<b>78</b>	<b>3,164</b>	<b>680</b>	<b>18,622</b>	<b>232,000</b>	<b>32</b>	

**THERMOPLASTIC AND PAINT QUANTITIES**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4400000000-E STATIONARY WORK ZONE SIGN SF	4405000000-E PORTABLE WORK ZONE SIGN SF	4415000000-N FLASHING ARROW BOARD EA	4420000000-N PORTABLE CHANGEABLE MESSAGE SIGN EA	4422000000-N PORTABLE CHANGEABLE MESSAGE SIGN (SHORT) DAY	4430000000-N DRUMS EA	4480000000-N TMA EA	4688000000-E 6" X 90 M WHITE THERMO LF	4688000000-E 6" X 90 M YELLOW THERMO LF	4690000000-E 6" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4700000000-E 12" X 90 M WHITE THERMO LF	4725000000-E THERMO MERGE ARROW 90 M EA	4815000000-E 6" WHITE PAINT LF	4815000000-E 6" YELLOW PAINT LF	4825000000-E 12" WHITE PAINT LF	4845000000-N PAINT MERGE ARROW EA	4900000000-N CRYSTAL & RED MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS EA								
I-5723	Johnston	1	I-40 EBL	EAST OF I-95 TO SAMPSON CO. LINE	1	2	MD	11	32	48	139	3	5	10	125	1	63,000	63,000	16,000		800		79,000	63,000	800			800								
		2	I-40 WBL	SAMPSON CO. LINE TO EAST OF I-95	1	2	MD	11	32	48	139			10	125		63,000	63,000	16,000		800		79,000	63,000	800			800								
		3	EBL ENTRY RAMP	NC 96 HWY TO EBL I-40	2	2		0.21	22								1,200	1200				3	1,200	1,200		3										
		4	EBL EXIT RAMP	I-40 TO NC 96 HWY	2	2		0.2	22								1,100	1100			37		1,100	1,100			15									
		5	WBL ENTRY RAMP	NC HWY 96 TO I-40	2	2		0.21	22								1,000	1000				3	1,000	1,000		3										
		6	WBL EXIT RAMP	I-40 TO NC HWY 96	2	2		0.21	22								1,200	1200			37		1,200	1,200			15									
<b>TOTAL FOR PROJ NO. I-5723</b>									<b>22.83</b>	<b>96</b>	<b>278</b>	<b>3</b>	<b>5</b>	<b>20</b>	<b>250</b>	<b>1</b>	<b>130,500</b>	<b>130,500</b>	<b>32,000</b>	<b>74</b>	<b>1,600</b>	<b>6</b>	<b>162,500</b>	<b>130,500</b>	<b>1,600</b>	<b>6</b>	<b>30</b>	<b>1,600</b>								
<b>GRAND TOTAL</b>																	<b>22.83</b>	<b>96</b>	<b>278</b>	<b>3</b>	<b>5</b>	<b>20</b>	<b>250</b>	<b>1</b>	<b>130,500</b>	<b>130,500</b>	<b>32,000</b>	<b>74</b>	<b>1,600</b>	<b>6</b>	<b>162,500</b>	<b>130,500</b>	<b>1,600</b>	<b>6</b>	<b>30</b>	<b>1,600</b>