

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.14.02.10871.1	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	3" MILLING SY	1½" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF	ADJ. OF DROP INLET EA
2016CPT.14.02.10871.1	Swain	1	US 74 WEST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	NO	NO	2.57	28	31,294		100	5,886	4,208	535	27,139	
TOTAL FOR MAP NO. 1										2.57		31,294		100	5,886	4,208	535	27,139	
2016CPT.14.02.10871.1	Swain	2	US 74 EAST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	NO	NO	2.57	28	30,758		100	5,786	4,156	527	27,139	
TOTAL FOR MAP NO. 2										2.57		30,758		100	5,786	4,156	527	27,139	
2016CPT.14.02.10871.1	Swain	3	US 74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	NO	NO	0.6	75	10,988		500	2,067	2,774	266		11
TOTAL FOR MAP NO. 3										0.6		10,988		500	2,067	2,774	266		11
2016CPT.14.02.10871.1	Swain	4	EXIT 64 RAMP	FROM US 19/74 EAST TO US 19	3	1		NO	NO	0.37	24	1,310			280	484	42		
TOTAL FOR MAP NO. 4										0.37		1,310			280	484	42		
2016CPT.14.02.10871.1	Swain	5	ACCESS RAMP WEST	FROM US 19 TO US 19/74 WEST	3	1		NO	NO	0.43	24	1,815			342	552	50		
TOTAL FOR MAP NO. 5										0.43		1,815			342	552	50		
2016CPT.14.02.10871.1	Swain	6	ACCESS RAMP EAST	FROM US 19 TO US 74 EAST	4	1		NO	NO	0.27	24		2,534			897	54		
TOTAL FOR MAP NO. 6										0.27			2,534			897	54		
TOTAL FOR PROJ NO. 2016CPT.14.02.10871.1										6.81		76,165	2,534	700	14,361	13,071	1,474	54,278	11
GRAND TOTAL										6.81		76,165	2,534	700	14,361	13,071	1,474	54,278	11

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E	4457000000-N	4697000000-E	4710000000-E	4721000000-E	4725000000-E		4810000000-E	4891000000-E		4905000000-N
										WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	8" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	4" WHITE PAINT LF	GENERIC PAVEMENT MARKING ITEM (50 MIL 4" YELLOW THERMOPLASTIC) LF	GENERIC PAVEMENT MARKING ITEM (50 MIL 4" WHITE THERMOPLASTIC) LF	SNOW PLOWABLE MARKERS EA
2016CPT.14.02.10871.1	Swain	1	US 74 WEST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	2.57	28	292.0	1	1,028	250	6	13	6	6,785	14,084	20,568	245
TOTAL FOR MAP NO. 1								2.57		292.0	1	1,028	250	6	13	6	6,785	14,084	20,568	245
2016CPT.14.02.10871.1	Swain	2	US 74 EAST	FROM BRIDGE #10 TO END DIV HWY	1	2	MD	2.57	28	292.0		1,028	250	6	15	2	6,785	14,084	20,568	245
TOTAL FOR MAP NO. 2								2.57		292.0		1,028	250	6	15	2	6,785	14,084	20,568	245
2016CPT.14.02.10871.1	Swain	3	US 74	FROM BEGIN DIV HWY TO PVT CHG .01 MILES WEST OF SR-1123	2	5	MU	0.6	75	67.0			80		2		3,168	7,920	8,160	94
TOTAL FOR MAP NO. 3								0.6		67.0			80		2		3,168	7,920	8,160	94
2016CPT.14.02.10871.1	Swain	4	EXIT 64 RAMP	FROM US 19/74 EAST TO US 19	3	1		0.37	24									2,442	3,981	
TOTAL FOR MAP NO. 4								0.37										2,442	3,981	
2016CPT.14.02.10871.1	Swain	5	ACCESS RAMP WEST	FROM US 19 TO US 19/74 WEST	3	1		0.43	24	24.0								2,838	4,627	40
TOTAL FOR MAP NO. 5								0.43		24.0								2,838	4,627	40
2016CPT.14.02.10871.1	Swain	6	ACCESS RAMP EAST	FROM US 19 TO US 74 EAST	4	1		0.27	24	24.0								1,785	2,905	40
TOTAL FOR MAP NO. 6								0.27		24.0								1,785	2,905	40
TOTAL FOR PROJ NO. 2016CPT.14.02.10871.1								6.81		699	1	2,056	580	12	30	8	16,738	43,153	60,809	664
GRAND TOTAL								6.81		699	1	2,056	580	12	30	8	16,738	43,153	60,809	664
															38		103,962			