

[†]2 :1 SLOPE -

#78M — STONE — BACKFILL

 ackslush GEOTEXTILE $\overline{ackslush}$

SECTION THRU SLAB


3'-0"

CORED

SLAB T

11/2" BACKER ROD

-2 LAYERS OF 30 LB. ROOFING FELT TO PREVENT BOND



NOTES

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, 4" Ø DRAINAGE PIPE, AND #78M STONE BACKFILL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.


*78M STONE BACKFILL (CLASS V SELECT MATERIAL) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

*78M STONE BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB.

FOR THE 4" Ø DRAINAGE PIPE OUTLET(S). SEE ROADWAY STANDARD DRAWINGS. AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL


APPROACH SLAB GROOVING IS NOT REQUIRED.

BE PAVED. SEE ROADWAY PLANS.



IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.

TEMPORARY DRAINAGE DETAIL



PLAN VIEW

TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)

SEAL (17230

: CACINEES

Wael Orafat

11/18/2015

B-4822 PROJECT NO._ TRANSYLVANIA COUNTY 15+10.00-L-STATION:

BILL OF MATERIAL

APPROACH SLAB AT EB #1

BAR | NO. | SIZE | TYPE | LENGTH | WEIGHT

301

300

728

1096

1396

1029

19.6

301

300

728

1096

1396

1029

19.6

LBS.

LBS.

C.Y.

LBS.

LBS.

C.Y.

26 | #4 | STR | 17'-4"

26 #4 STR 17'-3"

63 | #5 | STR | 11'-1"

63 #6 STR 11'-7"

APPROACH SLAB AT EB #2

BAR NO. SIZE TYPE LENGTH WEIGHT

26 | #4 | STR | 17'-4"

26 | #4 | STR | 17'-3"

63 | #5 | STR | 11'-1"

63 #6 STR 11'-7"

REINFORCING STEEL

CLASS AA CONCRETE

REINFORCING STEEL

CLASS AA CONCRETE

REINFORCING STEEL

***** EPOXY COATED

REINFORCING STEEL

* EPOXY COATED

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

BRIDGE APPROACH SLAB FOR PRESTRESSED CONCRETE CORED SLAB UNIT (SUB-REGIONAL TIER)

105° SKEW

	REVI:	SIO	NS		SHEET NO.
BY:	DATE:	NO.	BY:	DATE:	S-18
		3			TOTAL SHEETS
		4			18

- CURB END OF CURB WITHOUT SHOULDER BERM GUTTER

SPLICE LENGTHS					
BAR SIZE	EPOXY COATED	UNCOATED			
#4	2'-0"	1'-9"			
#5	2′-6″	2'-2"			
#6	3'-10"	2'-7"			

CHECKED BY: V. X. NGUYEN DATE : 4-15 MAA/AAC MAA/TMG DRAWN BY : SHS/MAA 5-09 REV. 12-11 REV. 8-14 CHECKED BY : BCH 5-09

ASSEMBLED BY: H.T.BARBOUR DATE: 4-8-15

ROADWAY-

APPROVED WIRE BAR - SUPPORTS @ 3'-0"CTS.

NORMAL TO END BENT

17-NOV-2015 16:27
X:\Structures\finalplans\B4822_SD_AS.dgn
warafat

#4A2 -

11/2:1 SLOPE
OR STEEPER
(TO BE DETERMINED
BY THE CONTRACTOR)

4"Ø PERFORATED — SCHEDULE 40 PVC PIPE