

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.04.20921.1	16	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	SHOULDER GRADING SMI	INCIDENTAL STONE BASE TONS	1½" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	CONCRETE CURB RAMP (STD. 848.06 and/or detail) EA	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF		
2016CPT.05.04.20921.1	Wake	1	SR 1010 - TEN TEN RD	SR 2727 - CROWDER RD TO 485' EAST OF SR 2722 - OLD MCCULLERS RD	2	2	NO	NO	3.462	26-40	688	6.88	179	60,207			5,333	320	347				500	1,250	5.00	1,632		
		2	SR 1107 - EAST ACADEMY ST	US 401 TO SR 2768 - JUDD PKWY	2,3	2	NO	NO	0.998	36					21,078			1,866	112	100							1,632	
		3	SR 1112 - SPENCE FARM RD	SR 1111 - OLD POWELL RD TO SR 1101 PINEY GROVE-WILBON RD	1	2	NO	NO	1.159	20-21	232		2.32	58			495	1,356	81	116				168	420	1.68		
		4	SR 1113 - WADE NASH RD	NC 55 TO SR 1101 - PINEY GROVE-WILBON RD SKIPPING NEW BRG PROJECT	1	2	NO	NO	1.636	20-28	334		3.05	84		189	450	1,903	114	164				243	610	2.43	408	
		5	SR 1115 - AVENT FERRY RD	JT. 2 MI NORTH OF 55 BYP TO END OF MAINT.	1	2	NO	NO	0.46	22-48	108		0.73	27		1,820	897	607	36	82				78	200	0.78	1,111	
		6	SR 1126 - HONEYCUTT RD	SR 1101 - PINEY GROVE-WILBON RD TO SR 1116 - CASS-HOLT RD	2	2	NO	NO	0.871	20	174		1.74	44		10,220			907	54	100				126	320	1.26	
		7	SR 1152 - HOLLY SPRINGS RD	850' S OF SR 1385 - LILLY ATKINS RD TO 75' N OF SR 1319 - JONES FRANKLIN RD SKIPPING FROM BAKERSFIELD TO CAMPBELL	1,4	2	NO	NO	1.524	24-52	241		2.41	61		1,463	605	3,113	187	152	3				176	440	1.76	1,752
		8	SR 1152 - W HOLLY SPRINGS RD	JT 500 FT EAST OF NC 55 TO NC 55 - MAIN ST	1	2	NO	NO	0.713	22-37	112		1.12	28		893	435	1,161	70	71				82	210	0.82		
		9	SR 1152 - HOLLY SPRINGS-NEW HILL RD	GREEN OAKS PKWY TO PVMT CHG	1	2	NO	NO	0.927	21-35	173		1.73	43		280	173	1,347	81	92			4	126	320	1.26		
		10	SR 1153 - TINGEN RD	SR 1011- SALEM ST TO US1	2	2	NO	NO	1.693	24-42	266		2.66	67		29,187			2,585	155	170				194	490	1.94	
		11	SR 1154 - WOODS CREEK RD	SR 1153 - OLD HOLLY SPRINGS-APEX RD TO SR 1149 - FRIENDSHIP RD	2	2	NO	NO	2.298	21	460		4.60	115		28,311			2,512	151	230				333	840	3.33	
		12	SR 1301 - SUNSET LAKE RD	.22 MI SOUTH OF SR 1152 - HOLLY SPRINGS RD TO US 401 - N MAIN ST	2	2	NO	NO	5.326	24-51	936		9.36	234		103,498			9,163	550	530				681	1,710	6.81	2,658
		13	SR 1303 - SMITH RD	SR 1010 - TEN TEN RD TO DEAD END	1	2	NO	NO	1.289	21-33	258		2.58	65				430	1,594	96	130				187	470	1.87	
		14	SR 1305 - ARTHUR PIERCE RD	SR 1152 - HOLLY SPRINGS RD TO .24 MI E OF SR 1300 - KILDAIRE FARM RD	1	2	NO	NO	0.764	20	153		1.53	39				460	833	50	76				111	280	1.11	
		15	SR 1375 - LAKE WHEELER RD	SR 1010 - TEN TEN RD TO US 401	1	2	NO	NO	3.927	24-50	785		7.85	196				1,460	5,490	329	393				569	5,616	5.69	792
		16	SR 1503 - DONNY BROOK RD	US 401 TO SR 1375 - LAKE WHEELER RD	2	2	NO	NO	0.7	20-21	140		1.40	35		9,922			880	53	70				101	260	1.01	408
		17	SR 1601 - JENKS RD	NC 55 TO 540 PROJECT LIMIT	2	2	NO	NO	0.758	20-32	83		0.83	21		14,557			1,289	77	76				61	160	0.61	408
		18	SR 1614 - SALEM CH RD	SR 1613 - DAVIS DR TO SR 1011- N SALEM ST	1	2	NO	NO	0.96	20-43	173		1.73	44		444	1,460	1,325	80	96		1			125	320	1.25	
		19	SR 1371 - LAKE WHEELER RD	SR 1370 - TRYON RD TO SR 1379 - PENNY RD SKIPPING NEW SECT. S OF MILL ENTRANCE	2	2	NO	NO	1.562	24-38	312		3.12	78		24,433			2,165	130	156				226	570	2.26	198
		20	SR 1375 - SIMPKINS RD	SR 1371 - LAKE WHEELER RD TO US 401	1	2	NO	NO	1.079	24-34	216		2.16	54				318	1,515	91	108				156	390	1.56	
TOTAL FOR PROJ NO. 2016CPT.05.04.20921.1									32.106		5,844	57.80	1,472	301,413	5,089	7,183	46,944	2,817	3,259	3	1	4	4,243	14,876	42.43	10,999		
GRAND TOTAL									32.106		5,844	57.80	1,472	301,413	5,089	7,183	46,944	2,817	3,259	3	1	4	4,243	14,876	42.43	10,999		