

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.05.05.10921.1	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	SHOULDER GRADING SMI	INCIDENTAL STONE BASE TONS	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	PORTABLE LIGHTING LS	TEMP SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
2016CPT.05.05.10921.1	Wake	1	US 1	98 BUS TO FRANKLIN CO.	1,3	4	NO	NO	2.61	54-90	1,070	10.70	535	678	1,780		10,734	633	600	0.42	780	1,950	7.80	1,850
		2	US 1	US 1 ALT TO SR 2045 - BURLINGTON MILL RD	1	4	NO	NO	2.00	76-130	800	8.00	400		1,545		9,492	560	400	0.37	580	1,450	5.80	2,545
		3	US 1 ALT	CHESTNUT AVE TO FRANKLIN CO	2	2	NO	YES	1.083	22-53	217	2.17	54		464	1,578		95	50	0.21	157	400	1.57	
TOTAL FOR PROJ NO. 2016CPT.05.05.10921.1									5.693		2,087	20.87	989	678	3,789	1,578	20,226	1,288	1,050	1.00	1,517	3,800	15.17	4,395
GRAND TOTAL									5.693		2,087	20.87	989	678	3,789	1,578	20,226	1,288	1,050	1.00	1,517	3,800	15.17	4,395

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LENGTH	WIDTH	4413000000-E	4457000000-N	4510000000-N	4685000000-E		4686000000-E		4695000000-E		4697000000-E	4710000000-E	4725000000-E					4770000000-E		4850000000-E	4900000000-N		4905000000-N
									WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	TEMPORARY TRAFFIC CONTROL LS	LAW ENFORCEMENT HR	4" X 90 M WHITE THERMO LF	4" X 90 M YELLOW THERMO LF	4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M WHITE THERMO LF	8" X 90 M YELLOW THERMO LF	8" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO MERGE ARROW 90 M EA	4" WHITE COLD APPLIED PLASTIC, TYPE III LF	4" YELLOW COLD APPLIED PLASTIC, TYPE III LF	4" LINE REMOVAL LF	CRYSTAL & RED MARKERS EA	YELLOW & YELLOW MARKERS EA	SNOW PLOWABLE MARKERS EA
2016CPT.05.05.10921.1	Wake	1	US 1	98 BUS TO FRANKLIN CO.	1,3	4	2.61	54-90	293	0.39		28,885	28,885	13,650	650	1,640			625	34	23	22	4		450	360	810	24	16	620
		2	US 1	US 1 ALT TO SR 2045 - BURLINGTON MILL RD	1	4	2.00	76-130	224	0.44	40	21,520	21,520	10,062	120	320			295	24	12	12	1	3						310
		3	US 1 ALT	CHESTNUT AVE TO FRANKLIN CO	2	2	1.083	22-53	122	0.17		11,653		380	12,335		156	810	27	3	1							12	91	
TOTAL FOR PROJ NO. 2016CPT.05.05.10921.1									639	1.00	40	62,058	50,405	24,092	13,105	1,960	156	810	947	61	36	34	5	3	450	360	810	36	107	930
GRAND TOTAL									639	1.00	40	62,058	50,405	24,092	13,105	1,960	156	810	947	61	36	34	5	3	450	360	810	36	107	930