PROJECT REFERENCE NO.	SHEET NO.
W-5518	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4, 5	-L- *SLOPE*	14+50	23+50	LT	4622
4, 5, 7	-L- *SLOPE*	15+00	23+00	RT	3927
5, 6	-L- *SLOPE*	25+00	34+50	LT	4943
5, 6, 7	-L- *SLOPE*	25+00	34+00	RT	4604
4	-L-	12+53	13+41	LT	100
4	-L-	13+00	13+41	RT	50
4	-L-	15+50	13+41	LT	235
4, 5	-L-	15+50	21+50	LT	420
5	-L-	24+90	29+50	RT	325
5	-L-	26+05	28+00	LT	140
5, 6	-L-	29+50	33+67	RT	295
5, 6	-L-	29+50	33+65	LT	290
6	-L-	33+65	35+50	LT	210
6	-L-	33+67	35+50	RT	210
				SUBTOTAL	20371
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					
				TOTAL	20371
				SAY	20400

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)