PROJ. REFERENCE NO.	SHEET NO.
W-5518	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
12+20.00000	0	0	0
12+50.00000	9	14	42
13+00.00000	23	50	42
13+50.00000	56	87	60
14+00.00000	66	127	50
14+50.00000	77	211	35
15+00.00000	104	314	18
15+50.00000	57	436	0
16+00.00000	0	620	0
16+50.00000	0	867	0
17+00.00000	0	1,116	0
17+50.00000	0	1,403	0
18+00.00000	0	1,776	0
18+50.00000	0	2,242	0
19+00.00000	0	2,758	0
19+50.00000	0	3,216	0
20+00.00000	0	3,622	0
20+50.00000	0	4,015	0
21+00.00000	0	4,375	0
21+50.00000	0	4,699	0
22+00.00000	0	4,965	0
22+50.00000	0	5,179	0
23+00.00000	0	4,049	0

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Embankment column does not include backfill for undercut.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
25+14.46000	0	0	0
25+50.00000	0	4,212	0
26+00.00000	0	5,803	0
26+50.00000	0	5,559	0
27+00.00000	0	5,328	0
27+50.00000	0	5,072	0
28+00.00000	0	4,747	0
28+50.00000	0	4,356	0
29+00.00000	0	3,907	0
29+50.00000	0	3,439	0
30+00.00000	0	2,932	0
30+50.00000	0	2,404	0
31+00.00000	0	1,930	0
31+50.00000	0	1,518	0
32+00.00000	0	1,185	0
32+50.00000	0	929	0
33+00.00000	0	707	0
33+50.00000	0	532	0
34+00.00000	53	406	0
34+50.00000	97	295	16
35+00.00000	79	178	35
35+50.00000	59	85	50
36+00.00000	29	31	45
36+50.00000	5	3	16